

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-109-20499-00-00  
Spot: SESWNE Sec/Twnshp/Rge: 23-11S-33W  
2970 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: SCHWARTZ E Well #: 1  
County: LOGAN Total Vertical Depth: 4700 feet

Operator License No.: 5123  
Op Name: PICKRELL DRILLING COMPANY, INC.  
Address: 100 S MAIN STE 505  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		2613		W/ 325 SACKS (CIRC)
PROD	4.5	4697	0	200 SX
SURF	8.625	311	0	190 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/19/2009 10:00 AM  
Plug Co. License No.: 5121 Plug Co. Name: MOBILE DRILLING COMPANY, INC.  
Proposal Rcvd. from: ED MONDERO Company: PRICKRELL DRILLING COMPANY, Phone: (620) 793-2315

Proposed Plugging Method: Ordered 360 sxs 60/40 pozmix - 4% gel - 300# hulls - 9 sxs gel.  
Plug through casing.  
152.75

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/19/2009 12:00 PM KCC Agent: DARREL DIPMAN

**Actual Plugging Report:**

8 5/8" surface casing set at 311' w/190 sxs cement.  
4 1/2" production casing set at 4697' w/200 sxs cement.  
TD 4700'. PBTD 4660'. Stage collar at 2613' w/325 sxs cement.  
Connected to 4 1/2" casing - pumped 75 sxs cement mixed with 300# hulls - followed with 9 sxs gel - followed with 200 sxs cement.  
Max. P.S.I. 400#. S.I.P. 250#.  
Connected to 8 5/8" surface casing - pumped 2 sxs cement.  
Max. P.S.I. 400#. S.I.P. 400#.

INVOICED

DATE 4-21-09  
INV. NO. 2009061419

**Perfs:**

Top	Bot	Thru	Comments
4630	4632		
4617	4624		
4273	4276		
4219	4222		

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 26 2009  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #43891.


Plugged through: CSG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM PT

STATE KANS COUNTY LOGAN 23-11S-33W  
 FIELD COOK SW-1/2 MI SE PROD (LANSING/CHEROKEE) SE SW NE  
 OPER PICKRELL DRLG 1 SCHWARTZ "E" 2970FSL 1650FEL SEC  
 WELL 1 SCHWARTZ "E" WELL CLASS WOE  
 API 15-109-20499-0000 STATUS OIL  
 SPUD 02/18/1991 COMP OIL  
 DTD 4700 LTD FTD MISS PSTD 04/05/1991



LOC 5 MI SW OAKLEY, KS

Petroleum Information Corporation

IPP 79 BOPD NO WTR  
 PROD ZONE: JOHNSON ZONE 4617-4632 GROSS  
 (CHEROKEE EXTENSION)

EL: 3127 KB 3122 GR

CSGS: 8 5/8 @ 316 W/ 190 SACKS  
 4 1/2 @ 4697 W/ 200 SACKS  
 MULTI STAGE COLLAR @ 2613 W/325 SX  
 TBGS: 2 3/8 @ 4640  
 DRLG COMP 3/1/91 RIG REL 3/1/91  
 DSTS: DST 1 4010-4064 HEEBNER/TORONTO  
 REC 255 FT MCW  
 INIT OP 30M IFF 20 FFP 50  
 FINAL OP 1H30M IFF 71 FFP 131  
 ISIP 1263 1H FSIP 1263 1H30M  
 DST 2 4135-4162 LANSING  
 REC 10 FT SOCM  
 INIT OP 30M IFF 10 FFP 10  
 FINAL OP 30M IFF 20 FFP 20  
 ISIP 121 30M FSIP 60 30M

LOG TOPS:  
 STONE CORRAL AN 2605 +522  
 BSE STN CORL AN 2629 +498  
 HEEBNER 4029 -902  
 TORONTO 4054 -927  
 LANSING 4072 -945  
 MUNCIE CREEK 4205 -1078  
 STARK SH 4286 -1159  
 MARMATON 4378 -1251  
 PAWNEE 4487 -1360  
 FT SCOTT 4543 -1416  
 CHEROKEE SH 4571 -1444  
 JOHNSON ZONE 4615 -1488  
 MISS 4677 -1550  
 TD 4700 -1573

KS 14-050791

CONTINUED

Copyright 1991 Petroleum Information Corporation

KS 14-050791

PICKRELL DRLG 1 SCHWARTZ "E"

DSTS: DST 3 4201-4229 MUNCIE CREEK  
 REC 60 FT GAS 60 FT OIL 120 FT G&MCO (60% OIL)  
 60 FT OCM (10% OIL) 60 FT MCW  
 INIT OP 30M IFF 40 FFP 71 FINAL OP 1H30M IFF 91 FFP 121  
 ISIP 1005 1H FSIP 956 1H30M  
 DST 4 4257-4281 MUNCIE CREEK  
 REC 300 FT GAS 60 FT GCO 60 FT GMCO (60% OIL) 240 FT GMCO (50% OIL)  
 INIT OP 30M IFF 40 FFP 70 FINAL OP 1H IFF 101 FFP 121  
 ISIP 996 1H FSIP 976 1H  
 DST 5 4289-4315 STARK REC 5 FT MUD 120 FT MCW  
 INIT OP 30M IFF 20 FFP 20 FINAL OP 1H30M IFF 40 FFP 60  
 ISIP 806 1H FSIP 737 1H30M  
 DST 6 4570-4637 CHEROKEE/JOHNSON ZONE  
 REC 780 FT GAS 840 FT GCO 120 FT MCO (70% OIL) 240 FT MCO (60% OIL)  
 INIT OP 30M IFF 80 FFP 223 FINAL OP 1H IFF 264 FFP 429  
 ISIP 1075 1H FSIP 1015 1H30M

PERFS: JOHNSON ZONE PERF W/ 4/FT 4617-4632 GROSS  
 4617-4624 4630-4632  
 ACID 500 GALS 15% DSFE  
 NO CORES

OPER ADDRESS: 110 N MARKET, STE 205, WICHITA, KS 67202

CONTR: PICKRELL DRLG RIG# 10 GEOL: TOM FUNK