

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21936-00-00
Spot: SENEWSWE Sec/Twnshp/Rge: 26-26S-32W
904 feet from S Section Line, 1416 feet from E Section Line
Lease Name: DUESING Well #: 5-O26-26-32
County: FINNEY Total Vertical Depth: 5275 feet

Operator License No.: 32309
Op Name: PRESCO WESTERN LLC
Address: 5665 FLATIRON PKWY
BOULDER, CO 80301

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4260		WITH 2 SX CMT
PC		3251		
PROD	5.5	5273	2517	WITH 175 SX CMT
SURF	8.625	1709		WITH 725 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/02/2009 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: SET CIBP @ 4260' WITH 2 SX CMT. LOAD HOLE WITH GEL WATER @ 1740' WITH 50 SX CMT. PLUG AT 960' WITH 40 SX CMT. PLUG AT 400' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.
171.44

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/03/2009 10:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4260' WITH 2 SX CMT. 1ST PLUG AT 1740' WITH GEL & 50 SX CMT. 2ND PLUG AT 960' WITH 40 SX CMT. 3RD PLUG AT 400' WITH 30 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4990	4995		MORROW
4800	4801		ATOKA
4789	4791		ATOKA
4460	4470		KC
4309	4318		LANSING

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

RECEIVED
MAR 10 2009
KCC DODGE CITY

Signed Ken Jehlik
(TECHNICIAN)