

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21384-00-00
Spot: SWSENW Sec/Twnshp/Rge: 21-22S-7W
2970 feet from S Section Line, 3630 feet from E Section Line
Lease Name: RICHARDSON Well #: 1-21
County: RENO Total Vertical Depth: 3600 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3599	2736	150 SXS CMT
SURF	8.625	263		185 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/26/2009 5:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: RAMA OPERATING COMPANY Phone: (620) 938-2943

Proposed Plugging Method: PER KCC RULES & REGULATIONS

117.00

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 02/26/2009 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

CIBP SET AT 2900, 5 SXS OF CEMENT SPOTTED ON TOP. RIPPED CASING OFF AT 2736' PULLED TO 1052' SPOTTED 35 SXS OF CEMENT, PULLED CASING TO 579' SPOTTED 35 SXS OF CEMENT, PULLED CASING TO 301' SPOTTED 35 SXS OF CEMENT, PULLED CASING TO 64' AND CIRCULATED 40 SXS OF CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3500	3504		
3476	3484		

INVOICED
DATE 4-21-09
INV. NO. 2009061422
RECEIVED
KANSAS CORPORATION COMMISSION
MAR 26 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: CEMENT WAS FROM COPELAND 60/40 - 4% GEL POS-MIX. TICKET #35297. TUBING STUCK IN HOLE AT 2943'.

Plugged through: CSG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

PKT

JK