

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-23023-00-01  
Spot: NWNESW Sec/Twnshp/Rge: 10-16S-15W  
2310 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: SCHEUERMAN Well #: 1  
County: BARTON Total Vertical Depth: 3530 feet

Operator License No.: 4952  
Op Name: SCHLOBOHM, STARR F.  
Address: 10 GREENLEAF DR  
WOLFEBORO, NH 03894

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3529	0	w/150 sxs cmt
SURF	8.625	268	0	w/165 sxs cmt

Well Type: EOR UIC Docket No: E25520.1 Date/Time to Plug: 03/18/2009 8:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: JOHN DRISCOLL Company: SCHLOBOHM, STARR F. Phone: (785) 483-9580

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 300# hulls - 11 sxs gel.  
114.73

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/18/2009 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Tied to casing - pumped 75 sxs cement with 300# hulls.  
Pumped 11 sxs gel - pumped 75 sxs cement.  
Shut down for 30 minutes.  
Pumped 50 sxs cement.  
Max. P.S.I. 300#. Shut in.

Perfs:

INVOICED  
DATE 4-21-09  
INV. NO. 2009061423

RECEIVED  
KANSAS CORPORATION COMMISSION

MAR 26 2009

CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #37489.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN) CM

Form CP-2/3

MAR 24 2009

PICT

JACK A. YOST D/B/A  
YOST OIL OPERATIONS  
BOX 811

#1 SCHEUERMAN

10-16-15W  
NW NE SW

RUSSELL, KS 67665

CONTR JOHN O. FARMER, INC.

CTY BARTON

GEOI.

FIELD WC (1-1/4 W OF  
GALATIA)


ELV 1974 KB SPD 2/7/83

CARD ISSUED 5/12/83

IP P 130 BOPD, NW

API 15-009-23,023

LANS 3388-3394



LOG	Tops	Depth/Datum	
HEEB	.....	3146-1172	8 5/8 " 268/165SX; 4 1/2 " 3529
TOR	.....	3164-1190	DST (1) 3267-3317 (LANS) / 45-45-45-45, REC 1860' SW, SIP 1033-1017#, FP 101-689 / 704-882#, HP 1765-1751#
DCUG	.....	3179-1205	DST (2) 3340-3405- (LANS) / 30-45-30-45, REC 885' MCO, SIP 1168-1159#, FP 293-227 / 294-396#, HP 1839-1831#
LANS	.....	3206-1232	DST (3) 3450-3500 (PENN CONG, ARB) / 30-45-30-45, REC 1560' SW, SIP 1050-1050#, FP 160-530 / 563-697#, HP 1889-1871#
BKC	.....	3436-1462	MICT - CO, PF (LANS) 3388-3394, AC 500 G (15%), SWB DWN, GSO, POP, P 130 BOPD (GR 43'). NW
PENN CONG	.....	3448-1474	
ARB	.....	3469-1495	
RTD	.....	3530-1556	

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS