

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21635-00-00
Spot: S2S2NE Sec/Twnshp/Rge: 21-14S-16W
2955 feet from S Section Line, 1370 feet from E Section Line
Lease Name: DREILING A Well #: 5
County: ELLIS Total Vertical Depth: 3393 feet

Operator License No.: 4787
Op Name: TDI, INC.
Address: 1310 BISON RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3375	0	w/100 sxs cmt
SURF	8.625	208	0	w/160 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/25/2009 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TOM DENNING Company: TDI, INC. Phone: (785) 628-2593

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel - 500# hulls.
Casing leaks. PC at 990'.

110.27

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/25/2009 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing to 3000'.
Allied rigged to tubing - pumped 15 sxs gel followed with 50 sxs 60/40 pozmix - 4% gel and 300# hulls mixed in.
Pulled tubing to 1250'. Allied rigged to tubing - pumped 120 sxs cement with 200# hulls to circulate cement to pit area.
Pulled tubing - topped off 5 1/2" casing with 15 sxs 60/40 pozmix - 4% gel.
Hole standing full. Rigged to 8 5/8" casing and pumped 10 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3268	3270		
3245	3247		
3128	3132		

INVOICED
DATE 4-21-09
INV. NO. 2009061424

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 26 2009

Remarks: ALLIED CEMENTING COMPANY-TICKET#36284.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

CM

MAR 25 2009

PCT

D OIL OPERATIONS & TEAM OIL

R.R. #1

#5 DREILING A

21-14-16W

C S/2 S/2 NE

VICTORIA, KS 67671
 CONTR REVLIN DRILLING CTY ELLIS

GEOL JERRY GREEN FIELD DREILING

E 1862 KB CM 2/5/79 CARD ISSUED 5/5/79 IP P 60 BOPD, NW

API 15-051-21,635

ARB 3364-80 OA

+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
ANH		960	+ 902
B ANH		998	+ 864
TOP		2834	- 972
HEEB		3053	-1191
TOR		3072	-1210
LANS		3100	-1238
BKC		3338	-1476
ARB		3362	-1500
LTD		3376	-1514
RTD		3380	-1518

8-5/8" 208/160sx, 5 1/2" 3375/100sx
 NO DST'S
 MICT - CO, (ARB OH), B/1 BOPD, AC 50,
 FU 750' FL, NW, PF (ARB) 16/3364-68,
 NAT, B/2 1/2 BF, NW/30", WKEND FU
 1873 FL, NW, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS