

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-20120-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 22-23S-4W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease Name: MILLER Well #: 1
County: RENO Total Vertical Depth: 3359 feet

Operator License No.: 5118
Op Name: TGT PETROLEUM CORPORATION
Address: 7570 W 21ST ST N STE1010D PO BOX 7
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	10.75	227		225
PROD	5.5	3352	2420	175 SX
SURF	8.625	604		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/23/2009 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE INC Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3300', AND 5 SKS CMT. REC. CASING, 50 SKS CMT AT 650' CIRC CMT FROM 280-0
109.17

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/23/2009 3:45 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE OPEN HOLE WAS FILLED TO 3300', AND CAPPED WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM 2420. AND PULLED TO 650', WHERE 50 SKS OF COMMON 3% CA CL WAS SPOTTED. WAITED 2 HOURS TAGGED CMT AT 610'. CIRCULATED CMT FROM 280',0'.

Perfs:

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 30 2009
CONSERVATION DIVISION
WICHITA, KS


INVOICED
DATE 4-21-09
INV NO. 2009061425

Remarks: QUALITY OIL WELL CEMENTING COMMON CEMENT

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

rs

PKT