

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-21852-00-03  
Spot: ~~E2~~<sup>SE</sup>SESW Sec/Twnshp/Rge: 14-27S-11W  
585 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: PARK Well #: 1  
County: PRATT Total Vertical Depth: 4500 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4270		WITH 6 SX CMT
CIBP		4377		
PROD	5.5	4499	1552	WITH 200 SX CMT
SURF	8.625	336		WITH 310 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/09/2009 2:00 PM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: LANCE FELLHOELTER Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: CIBP @ 4270' & 6 SX.CMT. LOAD HOLE WITH GEL. PLUG AT 1520' WITH 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT

146.25

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/09/2009 4:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4270' & PUT 6 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAY DOWN CASING & RUN 2 7/8" TBG TO PLUG THROUGH. LOAD HOLE WITH GEL. 1ST PLUG AT 1520' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 360' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4397	4400		
4298	4306		
3785	3788		
3732	3736		
3707	3710		

INVOICED  
DATE 4-21-09  
INV. NO. 2009061426

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 27 2009  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED  
MAR 11 2009

Signed

*Stephen J. Pfeifer*

(TECHNICIAN)

KCC DODGE CITY

Form CP-2/3