

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21870-00-00
Spot: SENE Sec/Twnshp/Rge: 14-27S-11W
3300 feet from S Section Line, 660 feet from E Section Line
Lease Name: PARK A Well #: 1
County: PRATT Total Vertical Depth: 4501 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4300		WITH 5 SX CMT
PROD	5.5	4500	1556	WITH 225 SX CMT
SURF	8.625	308		WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/04/2009 2:15 PM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: LANCE FELLHOELTER Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: SAND BACK TO 4300' & 4 SX CMT. LOAD HOLE WITH GEL. PLUG AT STUB WITH 50 SX CMT. PLUG AT ANHYDRITE WITH 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.
146.28

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/04/2009 4:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

LEFT STUCK DUMP BAILER IN HOLE ON TOP OF CIBP. SET CIBP @ 4300' & PUT 5 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID DOWN CASING & PLUG THROUGH 2 3/8" TBG. LOAD HOLE WITH GEL. 1ST PLUG AT 1550' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 330' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4322	4325		VIOLA

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 27 2009
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 4-21-09
INV. NO. 2009061426

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED
MAR 11 2009
KCC DODGE CITY

Signed Stephen P. Pfeifer
(TECHNICIAN)