

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-035-00798-00-01
 Spot: NWNWSW Sec/Twnshp/Rge: 10-34S-4E
2310 feet from S Section Line, 330 feet from W Section Line
 Lease Name: BALLINGER Well #: 1 OWWO
 County: COWLEY Total Vertical Depth: 3655 feet

Operator License No.: 33168
 Op Name: WOOLSEY OPERATING COMPANY, LL
 Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3460		
CIBP		3580		
PROD	4.5	3654	2224	150 SX
SURF	8.625	202		N/A

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 03/17/2009 11:00 AM
 Plug Co. License No.: 33728 Plug Co. Name: KING'S WELL SERVICE, LLC
 Proposal Rcvd. from: CARL W. DURR Company: WOOLSEY OPERATING CO Phone: (620) 886-5606

Proposed Plugging Method: AS PER KCC RECOMMENDATION.
 118.79

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
 Date/Time Plugging Completed: 03/17/2009 4:30 PM KCC Agent: SHANE JONES

Actual Plugging Report:

MIXED 25 SX OF GEL WITH 55 BBLs OF WATER AND LOADED THE HOLE. SET A CIPB @ 3125' AND CAPPED IT WITH 4 SX OF CLASS A CEMENT VIA DUMP BAILER. ATTEMPTED TO SHOOT OFF 4.5" CASING @ 2387' AT 12:40 PM. CASING NOT FREE AT THIS POINT. WENT BACK IN AND SHOT CASING OFF AT 2224' AT 1:30 PM. PULLED 66 JOINTS OF CASING AND RAN IN 9 JOINTS OF TUBING TO APPROX 265'. CIRCULATED TO SURFACE WITH 100 SXS OF CEMENT AT 4:30 PM.

Perfs:

Top	Bot	Thru	Comments
3584	3594		
3538	3550		
3510	3536		
3468	3502		
3376	3404		
3342	3366		
3176	3190		

INVOICED
 DATE 4-21-09
 INV. NO. 2009061429

RECEIVED
 KANSAS CORPORATION COMMISSION
 MAR 26 2009
 CONSERVATION DIVISION
 WICHITA, KS

Remarks: CONSOLIDATED OIL WELL SERVICES LLC USED COMMON CEMENT ON PLUGS TK #21525. 3/18/2009
CHECKED TOP PLUG FELL BACK 24' FILLED WITH 2 SXS CEMENT.

Plugged through: TBG

District: 02

Signed [Signature]
 (TECHNICIAN)

PLT