

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20819-00-00
Spot: E2NENWSW Sec/Twnshp/Rge: 10-13S-32W
2310 feet from S Section Line, 1260 feet from W Section Line
Lease Name: WIELAND Well #: 1
County: LOGAN Total Vertical Depth: 4670 feet

Operator License No.: 33629
Op Name: GREAT PLAINS ENERGY, INC.
Address: PO BOX 292
WAHOO, NE 68066

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4667		165 ASC
SURF	8.625	218		160 COMMON <u>151.78</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/15/2008 10:00 AM
Plug Co. License No.: 33755 Plug Co. Name: QUALITY PLUS OILFIELD SERVICES, LLC
Proposal Rcvd. from: HAROLD BELLERIVE Company: GREAT PLAINS ENERGY, INC. Phone: (785) 627-4531

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 03/21/2009 2:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

CIBP at 4400' w/5 sxs cement.
Perfed at 2500' - pumped 50 sxs 60/40 pozmix - 4% gel cement with 200# hulls.
Cut off casing at 1470' - pumped 100 sxs cement with 200# hulls.
Pulled to 220' and circulated with 50 sxs cement.
POOH. Topped off with 10 sxs cement.

Perfs:

Top	Bot	Thru	Comments
4574	4578		JOHNSON
4438	4446		PAWNEE

INVOICED
DATE 4-21-09
INV. NO. 2009041430

RECEIVED
KANSAS CORPORATION COMMISSION
APR 01 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Case Morris
(TECHNICIAN)

PM

MAR 31 2009