

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

*ACCEPT PA  
SP + research  
Sensu*

API Well Number: 15-009-20815-00-00

Spot: 228ENE

Sec/Twnshp/Rge: 31-18S-11W

3620 feet from S Section Line,

693 feet from E Section Line

Lease Name: KIMPLER B

Well #: 2

County: BARTON

Total Vertical Depth: 3420 feet

Operator License No.: 31561

Op Name: HOFFMAN, CHRIS DBA C & K OIL COM

Address: 410 B ST PO BOX 531  
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

PROD	4.5	3413	500	150 SX
------	-----	------	-----	--------

SURF	8.625	245	0	200 SX
------	-------	-----	---	--------

*111.15*

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/03/2009 10:00 AM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: CHRIS HOFFMAN

Company: C&K OIL COMPANY

Phone: (620) 786-8744

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 200# hulls.  
Casing to be pulled.  
Jacked on casing to get stretch - casing parted at 500'.  
Pulled casing and ran tubing to 1050'.  
Ran perfing tool in to bottom of tubing and perfed at 1060'.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/03/2009 2:00 PM

KCC Agent: BRUCE RODIE

**Actual Plugging Report:**

Sanded to 3350' and topped with 5 sxs cement.  
Ran tubing to 1050' - tied to tubing - pumped 75 sxs cement.  
Pulled tubing to 675' - pumped 35 sxs cement with 50# hulls.  
Pulled tubing to 350' - pumped 130 sxs cement with 150# hulls.  
Pulled tubing - hole stayed full.

**Perfs:**

Top	Bot	Thru	Comments
3409	3420		ARBUCKLE

**INVOICED**  
DATE 4-15-09  
INV. NO. 2009061395

**RECEIVED**  
KANSAS CORPORATION COMMISSIO  
**MAR 26 2009**  
CONSERVATION DIVISION  
WICHITA KS

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

*Bruce Rodie*

(TECHNICIAN)

CM

Form CP-2/3

MAR 24 2009

*POT*

AL TIPTON #2 KIMPLER "B" 31-18-11W  
 BOX 157, HAYS, KS. C N/2 SE NE  
 CONTR DUKE DRILLING CO. CTY BARTON

GEOL J. C. MUSGROVE FIELD KIMPLER

E 1828 KB CM 6/12/74 CARD ISSUED 7/3/74 IP P 70 BOPD N/W  
 ARB 3413-20, GR 42°

API 15-009-20,815

	+		+
	+		+

SMP	TOPS	DEPTH	DATUM
HEEB		2989	-1161
BR LM		3101	-1273
LANS		3114	-1286
CONG		3388	-1560
ARB		3409	-1581
RTD		3420	-1592

8-5/8" 201/150sx, 4½" 3413

NO LOG

DST (1) 3127-93/45-45-45-45, 600' GIP,  
 180' SO&GCM, 60' SO&GCWM, BHP 303-  
 478#, FP 63-159#

DST (2) 3412-3420/45-45-45-45, 240' GIP,  
 1560' OIL (42°), BHP 792-771#, FP  
 180-520#

MICT - CO TD, SD/12HRS, FU 2350' OIL,  
 SWB 13BOPH N/W/3HRS, POP

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS