

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19105-00-01
Spot: SWSESE Sec/Twnshp/Rge: 3-32S-7E
292 feet from S Section Line, 1088 feet from E Section Line
Lease Name: BARGER Well #: 3
County: COWLEY Total Vertical Depth: 2481 feet

Operator License No.: 33711
Op Name: B-C STEEL, LLC
Address: 209 N FRY ST
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	2480		
SURF	10.75	115		

80.63

Well Type: EOR UIC Docket No: E06985.2 Date/Time to Plug: 03/18/2009 8:00 AM
Plug Co. License No.: 33711 Plug Co. Name: B-C STEEL, LLC
Proposal Rcvd. from: ROGER FITZMORRIS Company: B-C STEEL LLC Phone: (620) 625-2999

Proposed Plugging Method: AS PER KCC RULES & REGS, 35 SXS @ BOTTOM, TAG CEMENT, PERFORATE @ 350' AND CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/18/2009 6:15 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2,054', RCCA MIXED & PUMPED 49 SXS CLASS A 2.5% CC AND DISPLACED IN CASING. PERFORATED SQUEEZE HOLES @ 350'. RIH W/TBG @ 351', RCCA MIXED & PUMPED 133 SXS 60/40 POZMIX 4% GEL, 2.5% CC TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 6:15 PM, 3-18-2009. RCCA TICKET #1478.

Perfs:

Top	Bot	Thru	Comments
2136	2152	CSG	CASING

INVOICED
DATE 4-22-09
INV. NO. 2009061431

RECEIVED
KANSAS CORPORATION COMMISSION
APR 02 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: CEMENT @ SURFACE ON BACKSIDE OF 7", CIBP @ 2165'.

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

JK

