

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-00034-00-00
Spot: NE Sec/Twnshp/Rge: 15-31S-42W
1320 feet from N Section Line, 1320 feet from E Section Line
Lease Name: COLLINGWOOD Well #: 1-15
County: MORTON Total Vertical Depth: 5310 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2750		WITH 2 SX CMT
CIBP		4500		WITH 2 SX CMT
PROD	5.5	5293	1554	WITH 150 SX CMT
SURF	8.625	1508		WITH 700 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/19/2009 12:00 PM
Plug Co. License No.: 32297 Plug Co. Name: SUPERIOR SERVICING, INC.
Proposal Rcvd. from: JOHN TRACY Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: SET CIBP @ 5000'. SET CIBP @ 2750' W/ 2SX CMT OR 400# HULLS & 25 SX CMT. SHOOT CASING @ 1530' OR DEEPER. PLUG AT 1530' WITH 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. 10 SX CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/19/2009 5:00 PM KCC Agent: JACK MACCLASKEY

Actual Plugging Report:

PER CHESAPEAKE: IN 1961 5 1/2" PERFORATED @ 3181' & SQUEEZED. EST. TOC @ 2550'. CIBP @ 4500' WITH 2 SX CMT. CIBP @ 2750' WITH 2 SX CMT. 1ST PLUG AT 1530' WITH 50 SX CMT. 2ND PLUG AT 550' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5148	5202		
5064	5122		
2865	2932		

INVOICED
DATE 4-22-09
INV. NO. 2009061433

RECEIVED
KANSAS CORPORATION COMMISSION
APR 02 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED
MAR 24 2009
KCC DODGE CITY

Signed Jack MacClaskey
(TECHNICIAN)