

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-22321-00-00  
Spot: NESESWNE Sec/Twnshp/Rge: 7-29S-15W  
2250 feet from N Section Line, 1350 feet from E Section Line  
Lease Name: KERR ESTATE Well #: 1  
County: PRATT Total Vertical Depth: 5000 feet

Operator License No.: 3532  
Op Name: CMX, INC.  
Address: 1551 N WATERFRONT PKWY STE 150  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2700		WITH 2 SX CMT
CIBP		3300		
PROD	4.5	3520	2012	WITH 340 SX CMT
SURF	8.625	392		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/19/2009 12:45 PM  
Plug Co. License No.: 34066 Plug Co. Name: TRINITY OILFIELD SERVICES INC.  
Proposal Rcvd. from: PRESTON DREILING Company: TRINITY OILFIELD SERVICES INC. Phone: (620) 564-3005

Proposed Plugging Method: CIBP @ 2700' WITH 2 SX CMT OR SAND TO 2700' WITH 4 SX CMT. PLUG AT 950' WITH 50 SX CMT. PLUG AT 420' WITH 60 SX CMT. PLUG AT 60' WITH 20 SX CMT.  
*162.50*

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/19/2009 1:45 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 2700' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 950' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 420' WITH 60 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3382	3385		
2753	2760		

INVOICED  
DATE 4-22-09  
INV. NO. 2009061434

RECEIVED  
KANSAS CORPORATION COMMISSION  
APR 02 2009  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED  
MAR 25 2009  
KCC DODGE CITY

Signed Stephen J Pfeifer  
(TECHNICIAN)

Form CP-278