

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20597-00-01
Spot: SWSWNE Sec/Twnshp/Rge: 21-31S-4E
3093 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HITTLE ESTATE Well #: 1-A
County: COWLEY Total Vertical Depth: 3442 feet

Operator License No.: 33367

Op Name: EXPLO OIL, INC.

Address: 2000 N. CENTRAL EXPRESSWAY, STE 2
PLANO, TX 75074

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3439		250 SX
SURF	8.625	222		150 SX

Well Type: SWD

UIC Docket No: D19126.0

Date/Time to Plug: 03/18/2009 8:00 AM

Plug Co. License No.: 31539

Plug Co. Name: SAMS WELL SERVICE, INC.

Proposal Rcvd. from: CHARLES MILLER

Company: EXPLO INC

Phone: (973) 312-0070

Proposed Plugging Method: AS PER KCC RULES & REGS

111.87

Plugging Proposal Received By: DUANE KRUEGER

Witness Type: PARTIAL

Date/Time Plugging Completed: 03/19/2009 10:35 AM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

CIRCULATED HOLE CLEAN @ 3212', PUMPED SAND ON BOTTOM. 3-19-2009
TAGGED SAND @ 3,000', WITH TBG @ 2970', CONSOLIDATED OILWELL SERVICES
PUMPED 6 SX GEL (300#) W/14 BBL FRESH WATER, FOLLOWED BY 5 SXS 60/40
POZMIX 4% GEL AND DISPLACED IN CASING. WITH TBG @ 295', CONSOLIDATED
MIXED & PUMPED 60 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT
CIRCULATED. PLUG DOWN 10:35 AM 3-19-2009. CONSOLIDATED CEMENT
TICKET #21029.

Perfs:

Top	Bot	Thru	Comments
3309	3379		

RECEIVED
KANSAS CORPORATION COMMISSION
APR 02 2009
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 4-22-09
INV. NO. 200 9061436

Remarks: CEMENT ON BACKSIDE OF 5-1/2" CASING @ SURFACE.

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)

JK

JK