

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-071-20188-00-02  
Spot: NWSENE Sec/Twnshp/Rge: 11-16S-43W  
3323 feet from S Section Line, 679 feet from E Section Line  
Lease Name: EDSALL E Well #: 3  
County: GREELEY Total Vertical Depth: 5320 feet

Operator License No.: 3273  
Op Name: LOEB, HERMAN L.  
Address: PO BOX 524  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5100		WITH 2 SX CMT
DVT		2822		WITH 150 SX CMT
PROD	5.5	5317	0	WITH 140 SX CMT
SURF	8.625	469		WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/11/2009 10:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: SHANE PELTON Company: HERMAN LOEB Phone: (618) 943-2227

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.  
172.90

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/11/2009 4:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 5100' WITH 2 SX CMT. TEST CASING TO 800 PSI. PERFORATE @ 1250'. INJECTION RATE 1.5 BPM @ 80 PSI. TIH W/2 3/8" TBG TO 2862'. PUMP 25 SX CMT AT 2862'. FULL CIRCULATION. PUMP 25 SX CMT AT 2022'. FULL CIRCULATION. TOOH W/TBG. PUMP 80 SX CMT, 150# HULLS, THEN 145 SX CMT DOWN 5 1/2" CASING THROUGH PERFS @ 1250' @ 350# UP TO 800#. NO BLOW OR CIRCULATION UP ANNULUS. HOLDING AT 300#. PUMP 125 SX CMT DOWN ANNULUS AT 200#. HOLDING AT 50#.

Perfs:

Top	Bot	Thru	Comments
5164	5180		

INVOICED  
DATE 4-22-09  
INV. NO. 2009061439

RECEIVED  
KANSAS CORPORATION COMMISSION  
APR 02 2009  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED

MAR 19 2009

KCC DODGE CITY

Signed

*Ken Jehlik*  
(TECHNICIAN)

Form CP 2/3