

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

#			

Locate well correctly on above
Section Plat

Treago County, Sec 13 Twp 11 Rge 24 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines CN 1/2 SE NW

Lease Owner Leo J. Dreiling Oil Co.

Lease Name Littlechild Well No. 3

Office Address Victoria, Ks.

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed Feb. 1, 1968

Application for plugging approved Feb. 1968

Plugging commenced Feb. 2, 1968

Plugging completed Feb. 4, 1968

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. Nichols

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	168'	None
				4 1/2	3970'	3024'

RECEIVED
STATE CORPORATION COMMISSION
FEB 2 1968
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with sand from 3939' to 3850'. Mixed and dumped 3 sx. of cement from 3850' to 3814'. Pulled casing. Mixed and pumped in 12 sx. of gel. Mixed and pumped in 100 sx. of cement from 1000' to 680'. Mixed and pumped in 12 sx. of gel from 680' to 180'. Mixed and pumped in 20 sx. of cement from 180' to 120'. Mixed and pumped in 1 sx. of gel from 120' to 40'. Mixed and pumped in 10 sx. of cement from 40' to base of the cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Russ Casing Pulling Inc.

Address Box 1082 Great Bend, Ks.

STATE OF KANSAS, COUNTY OF ELLIS, ss.

I, Leo F. Dreiling (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling

Leo F. Dreiling, Route 2, Victoria, Kansas 67671 (Address)

Subscribed and Sworn to before me this 9th day of February, 1968

September 19, 1970
commission expires

Joseph A. Hess Notary Public.



