

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

TREGO County. Sec. 12 Twp. 11 Rge. 24 (E) (W) EST

Location as "NE/CNW%SW%" or footage from lines SW SW SW

Lease Owner THEODORE GORE

Lease Name THOMAS LITTLECHILD Well No. 1

Office Address 400 BROWN BLDG., WICHITA 2, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed FEBRUARY 10 1957

Application for plugging filed FEBRUARY 10 (VERBAL) 1957

Application for plugging approved 19

Plugging commenced FEBRUARY 10 1957


Plugging completed FEBRUARY 10 1957

Reason for abandonment of well or producing formation

DRY HOLE

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well ELDON PETTY

Producing formation Depth to top Bottom Total Depth of Well 4360 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	169'	CEMENTED

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

BOTTOM PLUG SET AT 165' WITH 1/2 SACKS HULLS, 15 SACKS CEMENT.  
TOP PLUG SET AT 40' WITH 1/2 SACKS HULLS, 10 SACKS CEMENT.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor EMPIRE DRILLING COMPANY  
Address 400 BROWN BLDG., WICHITA 2, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK ss.  
I, DAN J. KORNFELD (CONTRACTOR FOR operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) DAN J. KORNFELD  
400 BROWN BLDG., WICHITA 2, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 19TH day of FEBRUARY, 19 57

My commission expires JUNE 7, 1960.

Charlotte Stanley, Notary Public.

PLUGGING  
FILE SEC 13 T 11 R24W  
BOOK PAGE 140 LINE 29

2-20-1957

LOG

COMPANY: THEODORE GORE, WICHITA, KANSAS

CONTRACTOR: EMPIRE DRILLING COMPANY, WICHITA, KANSAS

FARM: THOMAS LITTLECHILD NO. 1

LOCATION: SW SW SW OF SEC. 12-11-24, TREGO COUNTY, KANSAS

COMMENCED: JANUARY 26, 1957

COMPLETED: FEBRUARY 10, 1957

ELEVATION: 2395 K.B.

193	TO	1386	SHALE AND SHELLS	<u>TOPS:</u>	
1386	TO	1400	PYRITE		
1400	TO	1995	SHALE AND SAND	HEEBNER	3727'
1995	TO	2035	ANHYDRITE	TORONTO	3748'
2035	TO	2565	SHALE AND SHELLS	LANSING-K.C.	3766'
2565	TO	2990	SHALE AND LIME	BASE KANSAS CITY	4003'
2990	TO	3047	LIME AND SHALE	CHEROKEE GROUP	4178'
3047	TO	3180	SHALE AND LIME	BASAL PENNSYLVANIAN	
3180	TO	3250	LIME AND SHALE	CONGLOMERATE	4280'
3250	TO	3390	SHALE AND LIME	MISSISSIPPIAN	4305'
3390	TO	3520	SHALE AND SHELLS		
3520	TO	3670	LIME AND SHALE		
3670	TO	3735	SHALE AND LIME		
3735	TO	3955	LIME		
3955	TO	4065	LIME AND SHALE		
4065	TO	4255	SHALE AND LIME		
4255	TO	4345	SHALE		
4345	TO	4360	LIME		
4360			R.T.D.		

DRY AND ABANDONED

RAN ELECTRIC LOG

CASING: RAN 169 FT. OF 8 5/8" AND CEMENTED WITH 115 SACKS CEMENT.

CERTIFICATION


I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE THOMAS LITTLECHILD NO. 1, SW SW SW OF SEC. 12-11-24, TREGO COUNTY, KANSAS, AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

*Dan J. Kornfeld*  
 \_\_\_\_\_  
 DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 19TH DAY OF FEBRUARY, 1957.

*Charlotte Stanley*  
 \_\_\_\_\_  
 CHARLOTTE STANLEY, NOTARY PUBLIC

MY COMMISSION EXPIRES JUNE 7, 1960.



PLUGGING  
 FILE SEC 13 T 11 R24 W  
 POOK PAGE 140 LINE 29

RECEIVED  
 STATE COMMISSION  
 2-20-1957  
 FEELING  
 CONSERVATION