


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Trego County, Sec. 21 Twp. 11S Rge. 24 (E) (W) X
Location as "NE/CNW/SW" or footage from lines SW NW SE
Lease Owner Sunray DX Oil Company
Lease Name A. L. Struss Well No. 2
Office Address P. O. Box 729 Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 3-5-64 19
Plugging completed 3-11-64 19
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation Depth to top Bottom Total Depth of Well PB 4090 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	227	None
				5 1/2	None	15 1/2

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cleaning out cellar. Measuring T. D. Sanded to 4015' and 5 sacks of cement.
Rigging up jacks. Working pipe. Shot pipe at 3200'. Shot pipe at 2932'.
Working pipe.
Working pipe. Spotted 70 bbl. of oil.
Working pipe. Shooting and working pipe every 200'. Shooting and working pipe every 100' to 1524'. Pulling pipe.
Plugging well at 600' with 22 sacks of mud and 50 sacks of cement.
Pulling pipe.

RECEIVED
STATE CORPORATION COMMISSION
3-17-1964
MAR 17 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16 day of March, 19 64

My commission expires May 27, 1964

Notary Public

15-195-01492-00-00
WELL LOG

COMPANY SUNRAY MID-CONTINENT OIL COMPANY

SEC. 21 T. 11S. R. 24W

FARM STRUSS NO. 2


LOC NW, SW, SE

TOTAL DEPTH 4132'

COUNTY TREGO CO., KANSAS

LOGG. October 13, 1961 COMP. October 21, 1961

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8-5/8" @ 227' w/200 sax.
5 1/2" @ 4131' w/150 sax.

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

40	Top soil & sand
280	Shale
1200	Shale & shells
1580	Shale
1750	Sand
1880	Shale & red bed
2087	Red bed
2129	Anhydrite
2550	Shale
3200	Shale & lime
3270	Lime & shale
3375	Lime
3530	Shale & lime
3605	Lime & shale
4132	Lime
4132	T. D.

RECEIVED
STATE CORPORATION COMMISSION
Z-20-1964
FEB 20 1964

CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS }
County of BARTON }

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

do hereby state the above and foregoing is a true and correct copy of the log of the #2 STRUSS well.

Witnessed and sworn to before me this 8th day of November 1961

Notary Public, November 12, 1962

[Signature]
NOTARY PUBLIC