

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-00774-00-01

LEASE NAME Voda Unit

WELL NUMBER 2-R

330 Ft. from S Section Line

2,970 Ft. from E Section Line

SEC. 21 TWP. 11 RGE. 24 (W) or (W)

COUNTY Trego

Date Well Completed 6/27/61

Plugging Commenced 6/6/02

Plugging Completed 6/6/02

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR KCC Wichita Four-Way Operating, Inc.

ADDRESS P. O. Box 698, Great Bend, Kansas 67530

PHONE# (620) 792-2506 OPERATORS LICENSE NO. 5310

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 4, 2002 (date)

by Mr. Herb Deines and Mr. Richard Williams witnessed work. (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Lansing-K. C. Depth to Top 3,990' Bottom 4,039' T.D. 4,103'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	210'	None
				5 1/2"	4,100'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Ran tubing to 3,470'. Allied mixed 17 sx Gel blended with 100# hulls followed by 50 sx 60/40 pozmix cement blended with 10% Gel and 200# hulls displaced down the tubing. Pulled tubing to 1,700' and mixed 105 sx cement with 200# hulls circulated to surface. Pulled tubing out of hole and pumped 70 sx cement down 5 1/2" casing shut in with 100psi. Annulus held 1,500psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address P. O. Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Four-Way Operating, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(Employee of Operator) or (Operator) o


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) James W. Rockhold

James W. Rockhold

(Address) P. O. Box 698, Great Bend, Ks 67530

SUBSCRIBED AND SWORN TO before me this 13 day of June, 2002



My Commission Expires: April 4, 2003

Notary Public