

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
200 Colorado Derby Bldg.
202 W. 1st St.
Wichita, KS 67202

Trego County Sec. 22 Twp. 11s Rge. 24 W/W
Location as "NE/CNW/SW" or footage from lines
CE/2 SW SE

Lease Owner Liberty Enterprises, Inc.

Lease Name Struss Well No. #1

Office Address 308 West Mill Plainville, Ks 67663

Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed 8-12 1981

Application for plugging filed 8-12 1981

Application for plugging approved 8-12 1981

Plugging commenced 8:15 P.M. 8-12 1981

Plugging completed 10:00 P.M. 8-12 1981

Reason for abandonment of well or producing formation
No Commercial Production

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor
Producing formation Depth to top Bottom Tl. Depth of Well

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface casing	common	0'	203.77'	8 5/8"	203.77'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug #1 1000' with 60 sxs

Plug #2 200' with 40 sxs

Plug #3 40' with 10 sxs

5 sxs in rathole

Total-115 sxs 50-50 pos 6% gel

P.D. @ 10:00 P.M.

RECEIVED
STATE CORPORATION COMMISSION
9-2-1981
SEP - 2 1981


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pioneer Drilling Co, Inc.
308 West Mill Plainville, Ks 67663

CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Rooks, ss.

David L. Comeau (employee of owner) or (owner or operator) of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well is filed and that the same are true and correct. So help me God.



(Signature) David L. Comeau

(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of August, 1981

My commission expires 1-5-85

Judy Smith
Notary Public

15-195-20832-00-00

WELL LOG

OPERATOR: Liberty Enterprises, Inc.

WELL NAME: Struss #1 LOCATION: CE/2 SW SE 22-11s-24W

COUNTY: Trego STATE: Kansas

WELL COMMENCED: August 4, 1981 WELL COMPLETED: August 12, 1981

ELEVATION: 2459' K.B. TOTAL DEPTH: 4100'

PRODUCTION: D & A RIG NO: #3

CASING - 8 5/8": 7 Jts new 24# tallied @ 196.77' set @ 203.77' cemented with 125 sxs common
2 % gel 3 % cc P.D. @ 10:15 P.M. 8-4-81 did
5 1/2": _____ circ.

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0'	204'	cement, shales and sand	204' - 1 degree	
205'	240'	cement, shales and sand		
240'	1340'	sand and shale		
1340'	1575'	sand and shale		
1575'	1760'	sands		
1760'	1881'		1844' - 2 degree	
1881'	2048'	red bed -shale		
2048'	2090'	anhydrite		
2090'	2300'	shales		
2300'	2622'	shale		
2622'	2752'	shale	2633' - 1 1/2 degree	
2752'	2759'	shales and lime		
2759'	2844'	shales		
2844'	3100'	shale and lime		
3100'	3290'	shale and lime		
3290'	3483'	lime and shale		
3483'	3610'	lime and shale		
3610'	3738'	lime and shale		
3738'	3844'	lime and shale		
3844'	3920'	lime and shale		
3920'	3973'	lime and shale	3973' - 1 degree	
3973'	3990'	lime and shale		
3990'	3992'	lime and shale		
3992'	4065'	lime and shale		
4065'	4100'	lime and shale	4100' - 1 degree	
4100'	R.T.D.			

STATE OF KANSAS

COUNTY OF _____


The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct

PIONEER DRILLING CO., INC.

By Stacy A. Hilgers

SUBSCRIBED AND SWORN TO, BEFORE ME, This 28th day of August, 1981

Judy Smith
NOTARY PUBLIC



RECEIVED
STATE CORPORATION COMMISSION
9-2-1981
SEP - 2 1981

CONSERVATION DIVISION
Wichita, Kansas