

15-167-19277-00-03


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Russell County, Sec. 17 Twp. 11 Rge. (E) 15 (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines NESESE
Lease Owner Sohio Petroleum Company
Lease Name Stewart Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 8-8 19 42
Application for plugging filed 1-16 19 56
Application for plugging approved 1-18 19 56
Plugging commenced 4-10 19 56
Plugging completed 4-14 19 56
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production April 19 44
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3376 Feet
Show depth and thickness of all water, oil and gas formations. PBTD--3078'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				6 5/8	3142'	None
				8 5/8	2696'	248'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 15 sacks mud followed with Halliburton plug and 75 sacks Posmix Cement. Built rock bridge to 26'. Dumped 2 barrels cement into bottom of cellar.

RECEIVED
05 01-1956
DIVISION

Name of Plugging Contractor Barnes Csg. Pulling Co. (If additional description is necessary, use BACK of this sheet)
Address _____

STATE OF Kansas, COUNTY OF Russell, ss.
J. H. Bond (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. H. Bond
(Address) _____

SUBSCRIBED AND SWORN to before me this 30th day of April, 19 56

My commission expires January 24, 1959
Benedict B. Brown Notary Public.

PLUGGING
FILE SEC 17 T 11 R 15W
BOOK PAGE 32 LINE 2

15-167-1927700-03

Production Department

Russell, Kansas

March 20, 1956

DWS: 101

Mr. Lowell Smith
Gorham, Kansas

Re: AFE #15-5152
Plug and Abandon
Stewart #1

Approval has been obtained from the State Corporation Commission to plug and abandon the above well. Please contact Mr. Milton Galyardt, Box 145, Russell, Kansas, before plugging the well.

Sohio has a 31.25% W.I. in the well. The only salvable equipment is an estimated 500' of 8" casing in junk condition.

Pertinent Well Data

Lease & Well:	Stewart #1
Location:	NE SE SE Sec. 17-11S-15W
Original TD:	3228'
Deepened to:	3376'
Producing Horizon:	L-KC -- Open hole from 3142-3228'
Top of L-KC:	3007'
Casing:	2696' 8" - No cementing record
	3142' 6" - No cementing record
	100' 5" Liner from 3128-3228'
	123' 4" Liner from 3207-3330'

The well developed a casing leak in 1944 and a bridging plug was set at 3078' with no further attempts made to produce the well.

At a later date in 1944 attempts were made to salvage the 3142' string of 6" and the 2696' of 8" casing. These strings have no cementing records. The 6" was shot off at 2900' and 5 sacks cement dumped in hole at this depth. The 6" pulled in two between 500' and 600'. Pipe recovered was in a very poor condition and no further attempts were made to recover the remaining 6" or 8". The 8" is probably in two between 500' and 600'. Fifty barrels of rotary mud was dumped on top the 5 sacks cement plug which filled the hole.

Please proceed with the plugging at your convenience.

ORIGINAL SIGNED BY
D. W. SMITH

D. W. Smith
District Superintendent
Kansas District

jn:ds

cc: A. J. Yost
D. W. Smith

File

04-17-1956

COPY