

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: American Warrior, Inc.  
Address: P.O. Box 399  
Phone: (785) 398-2270 Operator License #: 4058  
Type of Well: Gas Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 03/02/2009 (Date)  
by: Richard Lacy (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Chase Depth to Top: 2190 Bottom: 2194 T.D. 2290'  
Chase Depth to Top: 2238 Bottom: 2241 T.D. 2290'  
\_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-135-24079 <sup>24136</sup> - 00-00  
Lease Name: Wells  
Well Number: 2-13  
Spot Location (QQQQ): SE - SW - \_\_\_\_\_  
640 Feet from  North /  South Section Line  
1960 Feet from  East /  West Section Line  
Sec. 13 Twp. 18 S. R. 21  East  West  
County: Ness  
Date Well Completed: 07/24/2001  
Plugging Commenced: 03/02/2009  
Plugging Completed: 03/02/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Chase	Gas & Water	2185	2260	8 5/8"	222'	None
				5 1/2"	2289'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Swift Services mixed and pumped 35 sacks of 60/40 poz, 4% gel with 100# of hulls and pumped down 2 3/8" tubing and spot @ 2112'. Pull tubing up to 1300' and Swift mix 125 sacks of 60/40 poz, 4% gel with 400# of hulls and pump down 2 3/8" tubing and circulate to surface. Pull tubing out of casing and Swift mix 25 sacks of 60/40 poz, 4% gel and fill casing up.  
Hook up to 8 5/8" casing Braden head and mix 15 sacks of 60/40 poz, 4% gel and pressure to 250 PSI and held. Job Complete.

Name of Plugging Contractor: Swift Services, Inc License #: 32382  
Address: N Highway 283, Ness City, KS 67560


KANSAS CORPORATION COMMISSION  
APR 06 2009  
RECEIVED

Name of Party Responsible for Plugging Fees: American Warrior, Inc.  
State of Kansas County, Ness, ss.

Scott Corsair (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) \_\_\_\_\_

(Address) 210 W Avenue A, Bazine, KS 67516



SWORN TO before me this 3rd day of April, 20 09

Denise Corsair My Commission Expires: 8-15-12  
Notary Public

PT