

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior, Inc.
Address: P.O. Box 399
Phone: (785) 398-2270 Operator License #: 4058
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 09/11/2008 (Date)
by: Mike Maier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Chase Depth to Top: 2198 Bottom: 2204 T.D. 3992'
Chase Depth to Top: 2228 Bottom: 2234 T.D. 3992'
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-135-24094-00-00
Lease Name: Wells
Well Number: 1-25
Spot Location (QQQQ): NW - NW - NE - NE *KCC PKT Per OP 2/3*
620 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 25 Twp. 18 S. R. 21 East West
County: Ness
Date Well Completed: 02/03/2000
Plugging Commenced: 03/03/2009
Plugging Completed: 03/03/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Chase	Gas & Water	2175	2250	8 5/8"	221'	None
				5 1/2"	4137'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Swift Services mixed and pumped 225 sacks of 60/40 poz, 4% gel down 5 1/2" casing with 300# of hulls. Shut in with 500 psi. Casing was full. Hooked up to 8 5/8" Braden head and tried to pump cement, pressured up to 600 psi and held. Job complete.

KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: Swift Services, Inc License #: 32382

APR 06 2009

Address: N Highway 283, Ness City, KS 67560

RECEIVED

Name of Party Responsible for Plugging Fees: American Warrior, Inc.

State of Kansas County, Ness, ss.

Scott Corsair (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

NOTARY PUBLIC - State of Kansas
DENISE CORSAIR
My Appt. Exp. 8-15-12

(Signature) _____
(Address) 210 W Avenue A, Bazine, KS 67516

SUBSCRIBED and SWORN TO before me this 3rd day of April, 20 09

Denise Corsair My Commission Expires: 8-15-12
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT