

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-00774-00-01
Spot: CSESESW Sec/Twnshp/Rge: 21-11S-24W
330 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: VODA UNIT Well Number: 2-R
County: TREGO Total Vertical Depth: 4103 feet

Operator License No.: 5310
Op Name: FOUR-WAY OPERATING, INC.
Address: PO BOX 698
GREAT BEND, KS 67530

Conductor Pipe: Size feet: 8/33.35
Surface Casing: Size 8.625 feet: 209 100 SX CMT
Production: Size 5.5 feet: 4100 60 SX CMT
Liner: Size feet:

Well Type: EOR UIC Docket No: E-15, 938 Date/Time to Plug: 06/06/2002 10:00 AM
Plug Co. License No.: 5310 Plug Co. Name: FOUR-WAY OPERATING, INC.
Proposal Rcvd. from: JAMES W. ROCKHOLD Company: FOUR-WAY OPERATING, INC. Phone: (620) 792-2506

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 17 sxs gel - 500# hulls.
D.V. Tool at 2095' w/275 sxs cement.
Perfs 3990' - 4060'. PBTD 4048'. FL 580'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/06/2002 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3500'.
Allied pumped 17 sxs gel spacer with 100# hulls, followed with 50 sxs 60/40 pozmix - 10% gel with 200# hulls.
Pulled tubing to 1700'.
Allied pumped 105 sxs cement with 200# hulls.
PTOH. Squeezed with 70 sxs cement.
Max. P.S.I. 300#. S.I.P. 100#.
Hooked up to backside - pressured to 1500#. (D.V. 2095' cwc.)

RECEIVED

JUN 17 2002
6-17-2002
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS MALINOWSKY #1. ALLIED CEMENTING COMPANY, OAKLEY, KANSAS.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

6-18-02
2002061983

Form CP-2/3

JUN 13 2002


PHILLIPS PETR _____ #1 MALINOWSKY _____ 21-11-24W
 SE SE SW
 Contr. _____ GARVEY DRLG _____ TREGO _____ County
 E 2500 _____ Comm. _____ Comp. 7-21-61 IP 32 BOPD/DRUM

E Log Tops	Depth	Datum
HEEB	3816	-1316
TOR	3836	-1336
LANS	3851	-1351
DRUM	3988	-1488
B/KC	4091	-1591
TD	4103	-1603

Casing
 8" 209
 5" 4100

PERF 4032-38: SWB 5.35 BO/3
 HRS: ACID 500: SWB 25.13 BO/
 1 HR: PERF 4011-18: BP 4025
 SWB 19.58 BO, 2.48 BW: PB 4048
 PMP 55 BO, 19 BW/24 HRS

VODA POOL



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS