

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-20142-00-00  
Spot: NWSESENW Sec/Twnshp/Rge: 31-21S-24W  
3174 feet from S Section Line, 3246 feet from E Section Line  
Lease Name: J. HUMMEL CB Well #: 1  
County: HODGEMAN Total Vertical Depth: 4483 feet

Operator License No.: 33190

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4467	0	WITH 75 SX CMT
SURF	8.625	469		WITH 275 SX CMT

Op Name: NOBLE ENERGY, INC.  
Address: 100 GLENBOROUGH DR STE 100  
HOUSTON, TX 77067

*KCC PCT per open*  
*ATTN: Julie Acevedo, 1625 Broadway Ste 2200, Denver, CO 80202*

*145.70*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/18/2009 8:30 AM

Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: TOM KARST Company: NOBLE ENERGY Phone: (785) 625-4052

Proposed Plugging Method: RUN TBG TO 4060', PUMP 150# HULLS & 35 SX CMT. TEST CASING. IF CSG TESTS OK, PERFORATE AT 800' & PUMP 80 SX CMT OVER CASING VOLUME. IF NO CIRCULATION, PUMP 150 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: ERIC MACLAREN  
Date/Time Plugging Completed: 03/18/2009 2:00 PM

Witness Type: COMPLETE (100%)  
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 3700' & PUMP 35 SX CMT & 150# HULLS. PULL TBG TO 1500' & PUMP 50 SX COMMON CMT W/3% CC. WAIT 2 HOURS. TEST CASING TO 500# & HELD. PERFORATED AT 800'. PUMPED 305 SX CMT & CIRCULATED TO PIT.

Perfs:

Top	Bot	Thru	Comments
4467	4483		

**INVOICED**  
DATE 4-23-09  
INV. NO. 2009061440

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 02 2009

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

CONSERVATION DIVISION  
WICHITA, KS

Plugged through: CSG

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED  
MAR 25 2009  
KCC DODGE CITY

*Form CP-2/3*  
*MA*