

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-20586-00-00
Spot: N2NWNE Sec/Twnshp/Rge: 20-31S-8W
330 feet from N Section Line, 1980 feet from E Section Line
Lease Name: BEAR Well #: 1
County: HARPER Total Vertical Depth: 4400 feet

Operator License No.: 32433
Op Name: ONSHORE, L.L.C.
Address: 200 E 1ST ST STE 301
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4286		
PROD	4.5	4393	2600	100 SXS CMT
SURF	8.625	375		175 SXS CMT

143.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/18/2009 2:00 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP AT 4286 AND 4 SKS OF CMT. REC PIPE, 35 SKS AT 1350, 35 SKS AT 900', CIRC CMT 425'-0'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/18/2009 3:44 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH A CIBP SET AT 4286', AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 2600' AND PULLED FROM THE WELLBORE. TUBING WAS RUN TO 1350', WHERE 35 SKS OF CMT WAS SPOTTED. THE TUBING WAS PULLED TO 900', WHERE 35 SKS OF CMT WAS SPOTTED. THE TUBING WAS PULLED TO 425 WHERE CMT WAS CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4394	4400		OPEN HOLE

INVOICED
DATE 4-23-09
INV. NO. 2009061441

RECEIVED
KANSAS CORPORATION COMMISSION
APR 02 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING 60/40 4% GEL
Plugged through: TBG

District: 02

Signed 
(TECHNICIAN)

AKT