

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-20429-00-00
Spot: S2NENWNE Sec/Twnshp/Rge: 36-26S-13W
4930 feet from S Section Line, 1650 feet from E Section Line
Lease Name: GRIFFITH Well #: 1
County: PRATT Total Vertical Depth: 4292 feet

Operator License No.: 9232
Op Name: TIMBERLINE OIL & GAS CORPORATIO
Address: 4000 PENROSE PL
RAPID CITY, SD 57702

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3920		
CIBP		4100		
PROD	4.5	4295	1220	WITH 250 SX CMT
SURF	8.625	428		WITH 350 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/20/2009 10:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: ED HARGER Company: TIMBERLINE OIL & GAS Phone: (620) 672-8239

Proposed Plugging Method: PLUG A T1600' WITH 50 SX CMT. TAG CMT. PLUG AT 810' WITH 15 SX GEL & 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.
139.49

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/20/2009 2:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

RAN BAILER ENCOUNTERED JUNK IN HOLE @ 1650'. FISHED OUT METAL TEE POST (WEDGED IN BOTTOM OF BAILER WHEN PULLED FROM HOLE). UNABLE TO GET BELOW 1650' W/REPEATED ATTEMPTS. ATTEMPT TO GET 4 1/2" CASING LOOSE JUST ABOVE JUNK @ 1650'. PIPE NOT FREE TO 1220'. SUSPECT SQUEEZED IN W/CMT. SPOT THROUGH 4 1/2" CASING. 1ST PLUG AT 1220' WITH 50 SX COMMON CMT W/3% CC. LET CMT SET. TAG TOP OF CMT AT 880'. 2ND PLUG AT 825' WITH 50 SX CMT. 3RD PLUG AT 450' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4184	4195		
4110	4112		
3927	3931		
3763	3769		

INVOICED
DATE 4-23-09
INV. NO. 2009061442

RECEIVED
KANSAS CORPORATION COMMISSION
APR 02 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

RECEIVED
MAR 25 2009
KCC DODGE CITY

Signed

Stephen J Pfeifer
(TECHNICIAN)

PKT