

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-00356-00-00
Spot: NESWNW Sec/Twnshp/Rge: 32-34S-33W
1750 feet from N Section Line, 880 feet from W Section Line
Lease Name: LIBERAL B Well #: 1
County: SEWARD Total Vertical Depth: 2721 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: PO BOX 1330
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2720	828	WITH 75 SX CMT
SURF	8.625	727		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/17/2009 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 250# HULLS & 25 SX CMT. 25 SX CMT AT 1600'. CIRCULATE CMT TO SURFACE @ 750'.
88.43

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/18/2009 10:15 AM KCC Agent: LINDLEY REIMER

Actual Plugging Report:
PUMP 300# HULLS & 20 SX CMT AT 2612'. PUMP 5 BBL GEL SPACER & 20 SX CMT AT 1600'. 1ST PLUG PUMPED 136 SX CMT AT 738'. TAGGED TOC @ 388'. 2ND PLUG PUMPED 104 SX CMT AT 368'. CMT CIRCULATED TO PIT.

Perfs:

Top	Bot	Thru	Comments
2682	2692		
2644	2652		
2612	2616		

INVOICED
DATE 4-27-09
INV. NO. 2009061444

RECEIVED
KANSAS CORPORATION COMMISSIO
APR 03 2009

Remarks: USED COMMON CEMENT BY SARGENTS.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: CSG

District: 01

RECEIVED
MAR 31 2009
KCC DODGE CITY

Signed [Signature]
(TECHNICIAN)

Form CP-273
[Signature]