

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-21294-00-00

Spot: SWSE

Sec/Twnshp/Rge: 13-23S-15W

660 feet from S Section Line, 3210 feet from W Section Line

Lease Name: JOHNSON

Well #: 1

County: PAWNEE

Total Vertical Depth: 4085 feet

Operator License No.: 32385

Op Name: CRISSMAN, KELLY F.

Address: 209 S MAIN ST

SAINT JOHN, KS 67576

String Size Depth (ft) Pulled (ft) Comments

PROD 4.5 4084 1325

SURF 8.625 282

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 03/23/2009 10:30 AM

Plug Co. License No.: 99981

Plug Co. Name: COPELAND ACID & CEMENT, INC.

Proposal Rcvd. from: TOM GARNER

Company: KELLY CRISSMAN

Phone:

Proposed Plugging Method: CIBP @ 3900' & 2 SX CMT. PLUG AT 930' WITH GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

132.76

Plugging Proposal Received By: STEVE DURRANT

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 03/23/2009 1:25 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

RAN TBG TO 3889' & PUMP 25 SX CMT WITH 200# HULLS. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 930' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 612' WITH 50 SX CMT. 3RD PLUG AT 28' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

KANSAS CORPORATION COMMISSION  
APR 06 2009  
RECEIVED

INVOICED

DATE 4-27-09

INV. NO. 2009061449

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

RECEIVED  
MAR 26 2009  
KCC DODGE CITY

Signed

Richard W. Lacey

(TECHNICIAN)

Form CP 273