

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-10086-00-00  
Spot: NESESE Sec/Twnshp/Rge: 18-32S-12W  
990 feet from S Section Line, 330 feet from E Section Line  
Lease Name: FORSYTH UNIT Well #: 2-1  
County: BARBER Total Vertical Depth: 4441 feet

Operator License No.: 3372  
Op Name: DIXON ENERGY, INC.  
Address: 8100 E 22ND N BLDG 300, STE 200  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4440	2500	WITH 100 SX CMT
SURF	8.625	200		WITH 135 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/13/2009 3:30 PM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SAND BACK TO 4340' & 5 SX CMT. PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. PLUG AT 230' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.  
144.33

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE  
Date/Time Plugging Completed: 03/13/2009 4:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SAND BACK TO 4340' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. LAY DOWN CASING & RUN 2 3/8" TBG IN TO PLUG THROUGH. 1ST PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 230' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4402	4404		
4392	4402		

INVOICED

DATE 4-27-09  
INV. NO. 2009061451

KANSAS CORPORATION COMMISSION  
APR 06 2009  
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED  
MAR 23 2009  
KCC DODGE CITY

Signed Stephen J. Pfeifer  
(TECHNICIAN)