

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-19141-00-00
Spot: NWSESWNW Sec/Twnshp/Rge: 12-34S-10E
3200 feet from S Section Line, 4550 feet from E Section Line
Lease Name: LEGRAND Well #: W3
County: CHAUTAUQUA Total Vertical Depth: 1550 feet

Operator License No.: 31124
Op Name: DOTY, TIM
Address: PO BOX 117
SEDAN, KS 67361

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|------|------------|-------------|---------|
| PROD | 5.5 | 1540 | | |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/28/2008 8:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' PLUG AT TD, 50' PLUG AT 900' AND 500' TO SURFACE INSIDE AND OUTSIDE PIPE.

50.38

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/29/2008 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1500' gelled hole and spotted 50' plug. Pulled 1" to 900' and spotted 50' plug. Pulled 1" up to 500' were casing had already been perforated and circulated cement to surface. Pulled 1" and topped well off. A total of 140 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

RECEIVED
KCC DISTRICT #3

APR 7 2009 DAS

CHANUTE, KS

INVOICED
DATE 4-27-09
INV. NO. 2009061452

RECEIVED
KANSAS CORPORATION COMMISSION

APR 10 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed

Duane A. Sims

(TECHNICIAN)

PKT