

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21553-00-00
Spot: W2NW Sec/Twnshp/Rge: 33-34S-20W
1333 feet from N Section Line, 790 feet from W Section Line
Lease Name: WOOLFOLK Well #: 1-33
County: COMANCHE Total Vertical Depth: 5600 feet

Operator License No.: 33513
Op Name: FIVE STAR ENERGY, INC.
Address: 215 E 14TH ST
HARPER, KS 67058

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	653		WITH 425 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/26/2009 5:00 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: GALEN ROACH Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 840' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

182.00

Plugging Proposal Received By: LINDLEY REIMER Witness Type: NONE
Date/Time Plugging Completed: 03/26/2009 7:00 AM KCC Agent: LINDLEY REIMER

Actual Plugging Report:

Perfs:

1ST PLUG AT 1200' WITH 50 SX CMT. 2ND PLUG AT 690' WITH 60 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

INVOICED
DATE 4-27-09
INV. NO. 2009061454

RECEIVED
KANSAS CORPORATION COMMISSION

APR 03 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED

MAR 31 2009

KCC DODGE CITY

Signed _____

(TECHNICIAN)