

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21011-00-00
Spot: SWSWSWSW Sec/Twnshp/Rge: 26-9S-20W
260 feet from S Section Line, 5020 feet from E Section Line
Lease Name: MARCOTTE Well #: 2
County: ROOKS Total Vertical Depth: 3875 feet

Operator License No.: 32158
Op Name: H & B PETROLEUM CORP.
Address: 130 E ROSS STE 103
CLEARWATER, KS 67026

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3873	0	w/100 sxs cmt
SURF	8.625	256	0	w/unknown sxs cmt
T1	2.875	3826		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/08/2009 9:00 AM
Plug Co. License No.: 34066 Plug Co. Name: TRINITY OILFIELD SERVICES INC.
Proposal Rcvd. from: AL HAMMERSMITH Company: H&B PETROLEUM CORP. Phone: (620) 564-3002

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 15 sxs gel.
PBTB 3839'. Log Tech perfed at 1115' and 1747'.
125.94

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/08/2009 11:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Trinity Oilfield Services RIH with tubing to 3518'.
Allied rigged to tubing - pumped 15 sxs gel, followed with 50 sxs 60/40 pozmix - 4% gel with 250# hulls mixed in.
Pulled tubing to 1750'. Allied rigged to tubing - pumped 150 sxs 60/40 pozmix - 4% gel with 250# hulls to circulate cement to steel tank.
Pulled tubing. Rigged to 5 1/2" casing - pumped 20 sxs 60/40 pozmix - 4% gel.
Max. P.S.I. 300#. S.I.P. 300#.
Rigged to 8 5/8" casing - pumped 10 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3824	3826		Arbuckle

INVOICED

DATE 4-27-09
INV. NO. 2009061455

RECEIVED
KANSAS CORPORATION COMMISSION
APR 10 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #036241.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

CM

PKT

replacement card

CORIE OIL CO
RUSSELL KS 67665

26-09S-20W
260'FSL & 260'FWL, SEC (IRREG)

#2 MARCOTTE

site: 1 S & 1-1/2 E OF PALCO KS	dy: ROOKS	API 15-163-21011
contr: EMPHASIS OIL OPER	field: NORTHAMPTON	
geol: LEWIS O CHUBB		
fr date 12/17/79	spd date 09/12/79	drig comp 09/17/79
	card issued 07/16/81	last revised 01/08/96

ELV: 2265 KB SMP

tops.....	depth/datum
SC.....	1734 + 531
TOP.....	3277 -1012
HEEB.....	3478 -1213
TOR.....	3498 -1233
LANS.....	3519 -1254
BKC.....	3743 -1478
MARM.....	3770 -1505
ARB.....	3824 -1559
RTD.....	3875 -1610

LOGGED

!P status:
OIL, ARB 3824-3826, 12/01/79
 CORR & INFO REL: 1/8/96 - ORIG FR 70'SW, C SW SW
 SW; WAS OIL WELL - TIGHT HOLE
 CSG: 8-5/8" 256, 5-1/2" 3873
 NO CORES OR DSTS
 MICT - CO, PF (ARB) 3824-3826 (EST), SO, POP, OIL
 WELL (POTENTIAL NOT RPTD), 12/1/79

COPYRIGHT 1995
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS