

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-20689-00-00
Spot: NENESW Sec/Twnshp/Rge: 11-22S-8W
2310 feet from S Section Line, 2310 feet from W Section Line
Lease Name: JUSTUS Well #: 2-A
County: RENO Total Vertical Depth: 3619 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S MAIN STE 420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3619	1400	50 SX
SURF	8.625	254		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/24/2009 8:00 AM
Plug Co. License No.: 33939 Plug Co. Name: BLACKGOLD OILFIELD SERVICE LLC
Proposal Rcvd. from: ROBIN BROWN Company: LOTUS Phone: (620) 546-4801

Proposed Plugging Method: AS PER KCC RULES AND REGULATIONS.

117-62

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/24/2009 2:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 3500' TOPPED WITH 4 SXS OF CEMENT. SHOT PIPE OFF AT 1400' PULLED CASING, RAN BACK IN WITH 2 3/8" TUBING TO 1216' SPOTTED 35 SX OF CEMENT, PULLED TUBING TO 685' SPOTTED 35 SX OF CEMENT, PULLED TUBING TO 312' AND CIRCULATED TO SURFACE WITH 110 SX OF CEMENT. CHECKED TOP PLUG ON 3/25/2009 OK TO CLOSE.

Perfs:

Top	Bot	Thru	Comments
3536	3560		

INVOICED
DATE 4-27-09
INV. NO. 2009061459

RECEIVED
KANSAS CORPORATION COMMISSION
APR 10 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING OUT OF GREAT BEND, TICKET #32683 - USING CLASS A COMMON CEMENT 2% GEL AND 3% CC. 15 LBS

Plugged through: TBG

District: 02

Signed BJ Hope
(TECHNICIAN)

JK

PK