

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Rama Operating Co., Inc.
Address: P.O. Box 159 Stafford, Kansas 67578
Phone: (620) 234-5191 Operator License #: 3911
Type of Well: Oil/Gas KCC PCT Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: B.J. Hope (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

API Number: 15 - 155-21,2110000
Lease Name: Beck
Well Number: 1-9
Spot Location (QQQQ): C - SE - SE - SE
330 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 9 Twp. 25 S. R. 9 East West
County: Reno
Date Well Completed: _____
Plugging Commenced: 3-24-09
Plugging Completed: 3-25-09

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	212'	None
				5-1/2"	4026'	2456'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.
Plugged off botm with sand to 3800' and 5 sxs. cement. Cut casing loose @2456', pulled up to 1469', pumped 15 sxs. gel and 35 sxs. cement, pulled up to 800', pumped 35 sxs. cement, pulled up to 265', pumped 35 sxs. cement, pulled up to 65' and circulated 35 sxs. cement to surface, 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524

KANSAS CORPORATION COMMISSION
APR 06 2009
RECEIVED

Name of Party Responsible for Plugging Fees: Rama Operating Co., Inc.
State of Kansas County, Rice, ss. _____
Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso
(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 3rd day of April, 20 09
Irene Herzberg My Commission Expires: _____
Notary Public

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-29-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PCT