

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Kelly Crissman

Address: 209 S. Main ST. John KS 67576

Phone: (620) 549-6244 Operator License #: 32385

Type of Well: GAS Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 3-20-2009 (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

Mississippi Depth to Top: 3937 Bottom: 3947 T.D. 4084

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-145-21294-0000

Lease Name: Johnson

Well Number: 1 *KCCPRT*

Spot Location (QQQQ): E2-W2 - SW - SE

660 Feet from  North  South Section Line

2810 3210 Feet from  East  West Section Line

Sec. 13 Twp. 23 S. R. 15  East  West

County: Pawnee

Date Well Completed: 8-15-1989

Plugging Commenced: 3-20-09

Plugging Completed: 3-23-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>Mississippi</u>		<u>3937</u>	<u>3947</u>	<u>4 1/2</u>		<u>1320'</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing into 3809' dumped a 25 sack balance blend with cotton seed hulls. Pulled out tubing. Cut casing at 1320' pulled casing to 932' dumped 15 sacks gel then 50 sacks cement. Pulled casing to 612' dumped 50 sacks cement. Pulled casing to 288' dumped 40 sacks. Pulled casing to 30' dumped 10 sacks.


Name of Plugging Contractor: Classic Well Service - Copeland Acid + Cement Inc License #: 32098 99981

Address: Box 539 Claflin KS 67525 *KCCPRT* KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: Kelly Crissman *Per CP2/3* **APR 03 2009**

State of \_\_\_\_\_ County, \_\_\_\_\_, ss. **RECEIVED**

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Kelly A. Criss

(Address) 209 S. MAIN ST JOHN, KS. 67576

SUBSCRIBED and SWORN TO before me this 27 day of March 2009

Tamera L. Ramsey My Commission Expires: 11-30-09  
Notary Public