

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: LARSON ENGINEERING, INC.
Address: 562 WEST STATE ROAD 4 OLMITZ, KS 67564-8561
Phone: (620) 653-7368 Operator License #: 3842

Type of Well: OIL Docket #: _____
(Oil, Gas, D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 6/17/2008 (Date)

by: CASE MORRIS (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

ARBUCKLE OPEN HOLE Depth to Top: 3278 Bottom: 3294 T.D. 3294

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-16375-00-00

Lease Name: SCHNEIDER B

Well Number: 11

Spot Location (QQQQ): C - S2 - S2 - NW

2310 Feet from North / South Section Line

1370 Feet from East / West Section Line

Sec. 14 Twp. 16 S. 14 East West

County: BARTON

Date Well Completed: SPUD 11/22/1939

Plugging Commenced: 6/24/2008

Plugging Completed: 6/26/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
ARBUCKLE	OIL	0	657	8-5/8	657	0
		0	3278	4-1/2	3278	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same, depth placed from (bottom), to (top) for each plug set.

CO 4-1/2" CSG TO 3230'. RU ALLIED. SPOTTED 7 SX GEL & 50 SX CMT W/ 100# HULLS @ 3230'. SPOTTED 75 SX CMT @ 1568'. SPOTTED 50 SX CMT @ 753' & CIRC CMT TO SURFACE. TRIED TO PUMP DOWN 8-5/8" & BLEW NIPPLE OFF CSG HEAD. PUMPED 50 SX CMT DOWN 4-1/2" CSG & CIRC CMT OUT 8-5/8" X 4-1/2" ANNULUS. PLUGGED W/ 225 SX 60-40 POZ W/ 4% GEL, 7 SX GEL & 100# HULLS.

Name of Plugging Contractor: EXPRESS WELL SERVICE & SUPPLY, INC. License #: 6426

Address: P.O. BOX 19 VICTORIA, KS 67671-0019

Name of Party Responsible for Plugging Fees: LARSON ENGINEERING, INC.

State of KANSAS County, BARTON, ss.

CAROL LARSON (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Carol Larson SECRETARY/TREASURER

(Address) 562 WEST STATE ROAD 4 OLMITZ, KS 67564-8561

DEBRA J. LUDWIG
Notary Public - State of Kansas
My Appt. Expires 5/5/2012

SUBSCRIBED and SWORN TO before me this 31ST day of MARCH, 2009

Debra Ludwig My Commission Expires: 5/5/2012
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION

APR 02 2009

CONSERVATION DIVISION
WICHITA, KS

PKT