

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 3273  
Name: Herman L. Loeb LLC  
Address 1: P.O. Box 838  
Address 2: \_\_\_\_\_  
City: Lawrenceville State: IL Zip: 62439 + 0524  
Contact Person: George Payne  
Phone: (812) 453-0385  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Perrnit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
CIBP Depth to Top: 3393' Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
KC Depth to Top: 3187' Bottom: 3308' T.D. 3393'  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 009-04917-0000  
NA - Drilled in 1957  
Spot Description: \_\_\_\_\_  
SW 2970 NE \_\_\_\_\_ Sec. 21 Twp. 20 S. R. 12  East  West  
2310 Feet from  North /  South Line of Section  
2310 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Barton  
Lease Name: Hulme Well #: B #2  
Date Well Completed: 1957  
The plugging proposal was approved on: 4/01/09 (Date)  
by: Case Morris (KCC District Agent's Name)  
Plugging Commenced: 4/01/09  
Plugging Completed: 4/03/09

KCC  
PKC  
per CP2/3

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8 5/8"	233'	0
			5 1/2"	3504'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

4/01/09 TIH to 3308'. RU Allied, pumped 11 sxs of gel followed by 75 sxs 60/40 4%, displaced w/ 10 bbl sw. TOOH. 4/03/09 Perf 2 holes @ 1400', 2 holes @ 650', 2 holes @ 150'. TIH w/ tbg to 1400'. RU Allied, mixed and pumped 125 sxs 60/40 4% and circ cement thru 5 1/2". Shut in 5 1/2", pumped 50 more sxs and circ cement thru 8 5/8". TOOH. Pumped thru 5 1/2" w/ 45 more sxs circ cement thru 8 5/8" again. Shut in 8 5/8", press up to 300#. Shut in 5 1/2". RDMO.

Plugging Contractor License #: 5893 Name: Pratt Well Service  
Address 1: P.O. Box 847 Address 2: \_\_\_\_\_  
City: Pratt State: KS Zip: 67124 + 0847  
Phone: (620) 672-2531  
Name of Party Responsible for Plugging Fees: Herman L. Loeb LLC  
State of KS County, Barton, ss.  
Alan Vratil  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Alan Vratil

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 07 2009

CONSERVATION DIVISION  
WICHITA, KS