


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Trego County. Sec. 25 Twp. 11S Rge. 24W (X) (W)
Location as "NE/CNW%SW%" or footage from lines NW NW NE
Lease Owner King Resources Company
Lease Name Charles Conner #1-25 Well No. #1-25
Office Address 324 North Robinson, Suite 200, Okla. City, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-11-66 19
Application for plugging filed 12-11-66 19
Application for plugging approved 12-11-66 19
Plugging commenced 12-11-66 19
Plugging completed 12-11-66 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4350 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	213'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set Plug @ 540' with 20 sacks cement
Set Plug @ 210' with 20 sacks cement
Set Plug @ 40' with 1/2 sk. hulls, 10 sks. cement

RECEIVED
STATE CORPORATION COMMISSION
12-15-1966
DEC 15 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite
P. O. Box 486, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of December, 1966

My commission expires April 1, 1967

Ulanda Nichols
Notary Public.

15-195-60000-00-00

RECEIVED
STATE CORPORATION COMMISSION

DRILLER'S LOG

DEC 15 1966
12-15-1966

COMPANY: CONSERVATION DIVISION
CONTRACTOR: Wichita, Kansas
FARM:
LOCATION:
COMMENCED:
COMPLETED:

King Resources
LEBEN DRILLING, INC.
CHARLES CONNER #1-25
NW NW NE SEC. 25-11S-24W
TREGO COUNTY, KANSAS
12-1-66
12-11-66

0	40	Clay, Shale
40	213	Sand, Shale
213	930	Shale
930	1060	Sand
1060	1620	Sandy Shale
1620	1989	Redbed
1989	2032	Anhydrite
2032	2300	Redbed, Shale
2300	2780	Shale, Lime
2780	3040	Lime, Shale
3040	3455	Shale, Lime
3455	3785	Lime, Shale
3785	4145	Lime
4145	4262	Lime, Chert
4262	4299	Lime
4299	4350	Lime, Chert
	<u>4350</u>	<u>RTD - D. & A.</u>

8 5/8" 8 rd. 20# new surface casing set @ 213' with 145 sacks of Common, 2% cc


I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Conner #1-25 Well, located NW NW NE of Section 25, Township 11 South, Range 24 West, of Trego County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 14th day of December, 1966.



Ulanda Nichols

Ulanda Nichols

My Commission Expires:
April 1, 1967