

15-195-21322-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-21,322-00-00

LEASE NAME Struss #1

WELL NUMBER SW NE NW

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 27 TWP. 11s RGE. 24w (W) of (W)

COUNTY Trego

Date Well Completed

Plugging Commenced 6/11/85

Plugging Completed 6/17/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Energy Exploration & Prod., Inc.

ADDRESS 5501 Foxridge Drive, Mission, Ks. 66202

PHONE#() OPERATORS LICENSE NO. 5639

Character of Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4120'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	289'	none
				4 1/2"	4120'	2516'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged bottom with 4 sacks cement, sand to 3950' & 4 sacks cement. Shot pipe at 2516' & pulled 62 joints of pipe. Plugged well with 29 gel mixed with 3 hulls, 100 cement mixed with 1 hull, 11 gel, 8 5/8 plug, & 80 sacks 50/50 poz 6% gel 3% c.c. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the well log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 2nd day of July, 1985

[Signature] Notary Public

My Commission Expires:



GREAT GUNS

Correlation Sonic Cement Bond Log

FILING NO.

COMPANY *Energy Exploration & Production*

WELL *Struss No.1*

FIELD _____

COUNTY *Trego*


STATE *Kansas*

Location: *SW-NE-NW*

RECEIVED
STATE CORPORATION COMMISSION
Other Services:
4-10-1985
APR 10 1985

Sec. *27* Twp. *11S*

Rge. *24E*



Permanent Datum *Ground Level*

Elev. *2478*

Elev. K.B. *2483*

Log Measured From *Kelly Bushing 5* Ft. Above Perm. Datum

D.F. *--*

Drilling Measured From *Kelly Bushing*

G.L. *2478*

Date	<i>9-15-83</i>		
Run No.	<i>one</i>	<i>one</i>	<i>one</i>
Type Log	<i>Gamma Ray</i>	<i>C.C.L.</i>	<i>Cement Bond</i>
Depth—Driller	<i>4120</i>	<i>4120</i>	<i>4120</i>
Depth—Logger	<i>4075</i>	<i>4075</i>	<i>4075</i>
Bottom Logged Interval	<i>4068</i>	<i>4065</i>	<i>4073</i>
Top Logged Interval	<i>3400</i>	<i>3400</i>	<i>3400</i>
Type Fluid In Hole	<i>water</i>		
Salinity, PPM CL			
Density			
Level	<i>Full</i>		
Max. Rec. Temp., Deg F.			
Operating Rig Time	<i>1 1/2 hr.</i>		
Equip No. & Location	<i>40 Hays</i>		
Recorded By	<i>D. Yunker</i>		
Witnessed By	<i>Portable Mast</i>		

FIELD
PRINT

BORE-HOLE RECORD				CASING RECORD			
Run No.	Bit	From	To	Size	Wgt.	From	To
<i>one</i>	<i>12 1/4</i>	<i>00</i>	<i>289</i>	<i>8 5/8</i>	<i>24</i>	<i>00</i>	<i>289</i>
<i>two</i>	<i>7 7/8</i>	<i>289</i>	<i>4120</i>	<i>4 1/2</i>	<i>10.5</i>	<i>00</i>	<i>N.A.</i>