


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Trego County, Sec. 29 Twp. 11 Rge. 24 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
SE NE SE

Lease Owner Icer Addis
Lease Name Reeder Well No. 1
Office Address P. O. Drawer 8038 Wichita, Kans. 67208
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Dry Hole
Date Well completed Dec. 20 1977
Application for plugging filed Dec. 20 1977
Application for plugging approved Dec. 20 1977
Plugging commenced Dec. 20 1977
Plugging completed 7:00 P.N. Dec. 20 1977
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Bathazon
Producing formation Depth to top Bottom Total Depth of Well 3945'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Plug at 950' W/70 sx 50/50 Pozmix, 6% Gel through open end DP
Middle Plug at 200' W/20 sx " " " thru DP Mud FO 400' with
solid bridge wood plug
10 sx to surface
2 sx in rat hole

Allied Cementing

RECEIVED
STATE CORPORATION COMMISSION
DEC 28 1977
12-28-1977
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

STATE OF Kansas COUNTY OF Barton, ss.
Gary Bagby (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gary Bagby Sterling, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 19 77

Bessie M. DeWerff Notary Public.

My commission expires 5-20-81

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY APPT. EXP. 5-20-81

15-195-2044-00-00

DRILLERS WELL LOG

L. D. DRILLING COMPANY - CONTRACTOR

ICER ADDIS - OPERATOR

REEDER # 1
SE NE SE 29-11-24
TREGO COUNTY, KANSAS

ELEV. 2515 KB
T.D. 3945

CASING

8-5/8" set at 221'

CEMENT

W/170 sx. 60/40 Pozmix, 2% Gel, 3% CC

COMMENCED: 12-14-77

COMPLETED: 12-20-77

FORMATION

DEPTH

Surface soil & sand	0 - 45
Shale W/sand streaks	45 - 216
Shale & Shells	216 - 1500
Red Bed	1500 - 1615
Dk. Sand	1615 - 1868
Shale & Lime	1868 - 2111
Anhy.	2111 - 2157
Shale & Lime	2157 - 2576
Lime & Shale	2576 - 3845
Shale	3845 - 3850
Lime & Shale	3850 - 3945

TOPS

Dk. Sand	1615
Anhy.	2110
Topeka	3611
Heeb.	3845
Toronto	3868
Lansing	3883

AFFIDAVIT

State of Kansas County of Barton

I, Gary Bagby of the L. D. Drilling Company

being first duly sworn on oath, State: That I have knowledge of the facts statements and matters herein contained and that the same are true and correct.

Gary Bagby
Gary Bagby

Subscribed and sworn to before me on this 23rd day of December 1977

My commission expires: 5-20-81

Bessie M. DeWerff
Notary Public: Bessie M. DeWerff

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY APPT. EXP. 5-20-81

RECEIVED
STATE CORPORATION COMMISSION
12-28-1977
DEC 28 1977
CONSERVATION DIVISION
Wichita, Kansas