

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-21,900-00-00

LEASE NAME Dodson

WELL NUMBER 1

2970 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 29 TWP. 11S RGE. 24 ~~KEXX~~(W)

COUNTY Trego

Date Well Completed 5-15-87

Plugging Commenced 5-15-87

Plugging Completed 5-16-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR N-B Company, Inc.

ADDRESS P. O. Box 506, Russell, KS 67665-0506

PHONE#(913) 483-5345 OPERATORS LICENSE NO. 6111

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #6

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4110'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	239'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Mud laden fluid 4110'-2100'

20 sks cement @ 2100'

10 sks cement @ 40'

100 sks cement @ 1200'

10 sks cement in rathole

40 sks cement @ 275'

10 sks cement in mousehole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]
Kyle B. Branum

(Address) P.O. Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 19th day of May, 19 87

Glenda R. Tiffin RECEIVED
STATE CORPORATION COMMISSION
Notary Public

My Comm. Expires: February 6, 1988



MAY 20 1987
5-20-1987
CONSERVATION DIVISION
Wichita, Kansas

15-95-21900-00-00

EMPHASIS OIL OPERATIONS

P. O. BOX 506

RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: N-B Company, Inc.
P. O. Box 506
Russell, Kansas 67665-0506

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Dodson

WELL #1

LOCATION: SW SE NW
Section 29-11S-24W
Trego County, Kansas

LOG TOTAL DEPTH: 4111'

ROTARY TOTAL DEPTH: 4110'

ELEVATION: 2513' K.B.

COMMENCED: 5/8/87

COMPLETED: 5/16/87

CASING: 8-5/8" @ 239' w/155 sks cement

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil, Sand & Clay	30'	Shale	2610'
Shale & Sand	340'	Shale & Lime	2830'
Shale	1320'	Shale	3220'
Sand	1405'	Shale & Lime	3430'
Shale & Sand	2040'	Lime & Shale	3958'
Shale	2113'	Lime (R.T.D.)	4110'
Anhydrite	2153'		


STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


Kyle B. Branum

Subscribed and sworn to before me on May 19, 1987.

My commission expires: February 6, 1988.




Glenda R. Tiffin, Notary Public

RECEIVED
STATE CORPORATION COMMISSION
5-20-1987
MAY 20 1987

CONSERVATION DIVISION
Wichita, Kansas