

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: LARSON ENGINEERING, INC.
Address: 562 WEST STATE ROAD 4 OLMITZ, KS 67564-8561
Phone: (620) 653-7368 Operator License #: 3842
Type of Well: OIL Docket #: _____
(Oil, Gas, D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 4/13/2009 (Date)
by: RICHARD WILLIAMS (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-195-01017 - 00-01
Lease Name: HUCK "A"
Well Number: 1 OWWO
Spot Location (QQQQ): 110' W OF - SE - SE - NE
2310 Feet from North / South Section Line
440 Feet from East / West Section Line
Sec. 36 Twp. 11 S. R. 21 East West
County: TREGO
Date Well Completed: _____
Plugging Commenced: 4/17/2009
Plugging Completed: 4/17/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
ARBUCKLE	OIL & WTR	3871'	3883'	8-5/8"	209'	0'
L-KC	OIL & WTR	3610'	3751'	5-1/2"	3924'	0'
PLATTSMOUTH	OIL & WTR	3489'	3508'			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same, depth placed from (bottom), to (top) for each plug set.

PLUGGED W/ 310 SX 60-40 POZ W/ 4% GEL, 15 SX GEL & 500# HULLS AS FOLLOWS:

PUMPED 10 SX CMT DOWN ANNULUS @ 100#. PUMPED DOWN CSG W/ 50 SX CMT W/ 200# HULLS, 15 SX GEL, 250 SX CMT W/ 300# HULLS, 600# MAX, SI W/ 300#. PLUGGING COMPLETE @ 10:00 AM, 4/17/2009.

KCC REPRESENTATIVE ON LOCATION: PAT STAAB

Name of Plugging Contractor: ALLIED CEMENTING CO., INC. License #: 99996 RECEIVED

Address: P.O. BOX 31 RUSSELL, KS 67665 APR 20 2009

Name of Party Responsible for Plugging Fees: LARSON ENGINEERING, INC. KCC WICHITA

State of KANSAS County, BARTON, ss.

CAROL LARSON (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Carol Larson SECRETARY/TREASURER

(Address) 562 WEST STATE ROAD 4 OLMITZ, KS 67564-8561

SUBSCRIBED and SWORN TO before me this 17TH day of APRIL, 2009

Debra J. Ludwig My Commission Expires: 5/5/2012
Notary Public

DEBRA J. LUDWIG
Notary Public - State of Kansas
My Appt. Expires 5/5/2012

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT