

10-12  
4-071010 15-051-24808-00-00

203  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-051-24,808  
SW SW NW /4 SEC. 19 , 11 S, 19 (W)  
2970 feet from S section line  
4950 feet from E section line

Operator license# 6569 Lease Rathbun well # 1

Operator: Carmen Schmitt County Ellis 117.29

Address: P.O. Box 47 Well total depth 3609 feet  
Great Bend, Kansas 67530 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 216 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Duke Drilling, Inc. License# 5929

Address: Great Bend, Kansas 67530

Company to plug at: Hour: A.M. Day: 12 Month: October Year: 92

Plugging proposal received from: Leonard Williamson

Company: Duke Drilling, Inc. Phone: 316-793-5100

Were: 8 5/8" - 216' S.P. cwc. w/135 sx. 60/40 pozmix - 2% gel. - 3% c.c. Allied Cementing. Arbuckle well - Elev. 1975' - No circulation problems, mud condition - vis. 47 wt. 9.0. Proposal 215 sx. 60/40 pozmix 6% gel. and 1 sx. flocele. Circulate hole - spot with drill stem - heavy mud between all plugs. 25 sx. @ 3500' - 25 sx. @ 1340' - 100 sx. with 1 sx. flocele @ 625' - 40 sx. @ 250' - 10 sx. @ 40'. 15 sx. rathole (circ.) 10 sx. in mousehole (circ.)

Plugging Proposal Received by: Marion J. Schmidt *MJS*  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 2:20P.M., Day: 12, Month: October, Year: 92

Actual plugging report: Duke Drilling ordered 215 sx. 60/40 pozmix - 6% gel. and 1 sx. of flocele. Circulated hole, spotted and displaced all cement through drill pipe, heavy mud between all plugs.

- 1st. plug @ 3500' w/25 sx. cement.
- 2nd. plug @ 1340' w/25 sx. cement.
- 3rd. plug @ 625' w/100 sx. cement and 1 sx. flocele
- 4th. plug @ 250' w/40 sx. cement. 15 sx. in rathole (circ.)
- 5th. plug @ 40' w/10 sx. cement. 10 sx. in mousehole (circ.)

Remarks: Condition of casing(in hole):GOOD  BAD  Anhy.plug:YES  NO  Dakota plug:YES  NO   
Bottom plug(in place):YES  ,CALC  ,NO  Plugged through TUBING  , CASING  . Elevation: 1975

RECEIVED  
STATE CORPORATION COMMISSION  
10-26-1992

I did[  ] / did not[  ] observe the plugging.

DATE 11-4-92  
36668

*Marion J. Schmidt*  
(agent)