

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 051-23746-00-00

SW, Sec. 1, T 11 S, R 19 W/E

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5465

Lease Name Billinger Well # 4 R

Operator: J. B. Collins  
Name &  
Address 1007 Cody  
Hays KS 67601

County Ellis

Well Total Depth 3660 feet \$118.95

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 175

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well (D&A)

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Dreiling Oil Inc. License Number 5145

Address victoria KS

Company to plug at: Hour: 11:30 A Day: 18 Month: 12 Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Everett Mickelson

(company name) Dreiling oil Inc. <sup>913</sup> (phone) 735-2204

were: order 220 sx cement 50/50 portmix 6% gel. 3% c.c.

1 sx. huls - 1-8 5/8 plug 1 sx Flow seal

Heavy mud between all plugs

ump cement down drill pipe.

Elev. 2086 Anhydrite 1424-61 Arbuckle 3652

Dakota 1575  
511 = 810

Signed Dale Balthazor  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ (None)

Operations Completed: Hour: 6: P Day: 18 Month: 12 Year: 19 83

ACTUAL PLUGGING REPORT circ. @ 3650 turn hole over

25 sx @ 3650

25 sx @ 1450

100 sx @ 810 with 1 sx flow seal

40 sx @ 220, 1 sx huls, push plug to 40'

10 sx @ 40

10 sx Rat hole

Remarks: 10 sx mouse hole.

cementing co. Allied

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED  
DATE 1-9-84  
REV. NO. 8128 W

RECEIVED  
STATE CORPORATION COMMISSION  
12-27-1983  
DEC 27 1983  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Dale Balthazor  
(TECHNICIAN)