

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25055-00-00
Spot: SWSWSWNW Sec/Twnshp/Rge: 1-11S-19W
2660 feet from S Section Line, 5130 feet from E Section Line
Lease/Unit Name: BILLINGER Well Number: 1
County: ELLIS Total Vertical Depth: 3687 feet

Operator License No.: 9860
Operator Name: CASTLE RESOURCES, INC.
Address: BOX 87
SCHOENCHEN, KS 67667

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 209
Production: Size feet: 119.83
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 9/26/00 10:00:00 PM
Plug Co. License No.: 30076 Plug Co. Name: A & A PRODUCTION
Proposal Rcvd. from: DARRELL ANDERSON Company: A & A PRODUCTION Phone: (785) 421-6266

Proposed Plugging Method: Order 215 sxs 60/40 pozmix - 6% gel with 1/4# floceal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HUBERT DEINES Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 09/27/2000 12:30 AM KCC Agent: HUBERT DEINES

Actual Plugging Report:

1st. Plug at 3650' w/25 sxs. - Arbuckle Top at 3681'.
2nd. Plug at 1475' w/25 sxs. - Anhydrite at 1450' - 1480'.
3rd. Plug at 775' w/100 sxs. - Dakota 459' -759'.
4th Plug at 260' w/40 sxs.
5th Plug at 40' w/10 sxs.
Rathole with 15 sxs.

RECEIVED
STATE CORPORATION COMMISSION
10-11-2000
OCT 11 2000
CONSERVATION DIVISION
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY

Plugged through:

District: 04

Signed  (TECHNICIAN)

INVOICED
DATE 10/13/00
WEL. NO. 2001060821

OCT 05 2000