

To: 6 040796
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 051-22,256-00-00
SW SW SW, SEC. 1, T 11 S, R 19 (W)

TECHNICIAN'S PLUGGING REPORT

Operator License # 5465

Operator: B J Oil Co.
Name & Address 2911 Canterbury
Hays, Kansas 67601

_____ feet from S section line
_____ feet from E section line

Lease Name Billinger Well # 1
County Ellis \$119.60

Well Total Depth 3680 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 161' w/135 sk

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____

Address Russell, Kansas

Company to plug at: Hour: 9:00 AM Day: 2 Month: Sept Year: 19 87

Plugging proposal received from Vernon Chard

(company name) B.J. Oil Company (phone) _____

were: 4 1/2" csg set at 3671' w/150 sks.

Perf 3509' - 3345'. D.V. at 1440' cement N. A. (circ. surface)

Sq at 884' and 1010' w/130 sks.

Ordered 150 sks 65/35 Poz 10% Gel 2% Lite and 1/4# Flocele and 6 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 PM Day: 2 Month: Sept Year: 19 87

ACTUAL PLUGGING REPORT

Pumped in 150 sks cement w/1/4# Flocele and 6 sks Hulls. Max PSI 1000# S.I. 500#

STATE CORPORATION COMMISSION

SEP 17 1987

9-17-1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED ~~XXXXXX~~ observe this plugging.

DATE 9-23-87

SER. NO. 18173

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel