

6 031559

6-20  
API NUMBER 15- 179-20,347 -0001  
SE NE NE, SEC. 9, T 9 S, R 27 (W)

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4290 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5146

Lease Name McFadden Well # 1  
County Sheridan 132.60

Operator: Rains & Williamson Oil Co. Inc.  
Name & Address 435 Page Ct.  
220 W. Douglas  
Wichita, Kansas 67202

Well Total Depth 4080 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 286

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well X D&A \_\_\_\_\_  
Other well as hereinafter indicated D-17,666

Plugging Contractor Halliburton License Number \_\_\_\_\_  
Address Oberlin, Kansas

Company to plug at: Hour: A.M. Day: 20 Month: 6 Year: 19 91

Plugging proposal received from A.D. Belt  
(company name) Rains & Williamson (phone) \_\_\_\_\_

were: 8 5/8 set @ 286' w/225 cwc. 4 1/2 set @ 4078 w/150 sx. Perfs. 3629-3991'  
Cement from 2300 cwc. Order 300 sx. 65/35 poz. 10% gel. Halliburton Cement  
Company - Hoxie Tank Service water. The backside w/cemented from 2300' -  
1300' - 790' - 770' with 500 sx. Tubing & packer pulled out of well w/hole  
open across perfs.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:00 A.M. Day: 20 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT Squeezed 4 1/2 w/245 sx. cement blend to max. P.S.I. 300#.  
Close in P.S.I. 150#. Squeezed 8 5/8 w/80 sx. cement blend to max. 300#.  
Close in P.S.I. 150#. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION  
7-24-91  
JUL 24 1991  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(to be observed) observe this plugging.

DATE 8-6-91  
INV. NO. 32573

Signed Carl Goodrow  
(TECHNICIAN)