

4-060954

E-23,099-0001

TO: 8-18  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-179-20,376<sup>9</sup>.0003

N2 NE NE /4 SEC. 09, 09 S, 27 W  
4950 feet from S section line  
660 feet from E section line

Operator license# 9860

Lease McFadden "A" Well # 1

Operator: Castle Resources

County: Sheridan

Address: 1200 East 27th Street  
Hays, Kansas 67601

Well total depth 4095 <sup>133.08</sup> feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 294 feet

Aband. oil well\_\_\_, Gas well\_\_\_, Input well X, SWD\_\_\_, D & A\_\_\_

Plugging contractor: Co Tools License# \_\_\_\_\_

Address: \_\_\_\_\_

Company to plug at: Hour: 12:15 P.M. Day: 18 Month: August Year: 1996

Plugging proposal received from: Kelly Branum

Company: Consultant To Castle Resources Phone: 913-625-5155

Were: Order 240 sxs 60/40 posmix - 10% gel - hulls - 14 sxs gel.

RECEIVED  
KANSAS CORPORATION COMMISSION

9-6-96  
SEP 06 1996


Plugging Proposal Received by: Herb Deines CONSERVATION DIVISION  
Plugging operations attended by agent? All[ ], Part[ ], None[ X ] WICHITA, KS

Completed: Hour: 1:00 P.M., Day: 18, Month: August, Year: 1996

Actual plugging report: 8 5/8" to 294' w/175 sxs. 5 1/2" to 4095' cwc with 150 sxs. D.V. at 1400' to surface - circulated with cement. Perfs 4005' - 4008'. Tied onto annulus with instant 500# S.I.P. Tied onto production casing and pumped 50 sxs cement with 400# hulls, 14 sxs gel and 190 sxs cement. Max. P.S.I. 800#. S.I.P. 400#.

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD X BAD \_\_\_\_\_ Anhy.plug: YES X NO \_\_\_\_\_  
Bottom plug(in place): YES \_\_\_\_\_, CALC X, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING X. Elevation: 2693 GL

I did/did not [ X ] observe the plugging.

  
RK (agent)  
Form CP-2/3

INVOICED

DATE SEP 09 1996

INV. NO. 46447

8-18